



OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)

AND

COUNTY BOARD OF SUPERVISORS

County Panola
Project No. LSBP-54(32)
Road Name. CROUCH ROAD

BIDS RECEIVED: Panola County Courthouse in Batesville, MS on Friday, May 10, 2024 @ 10:00 am

Project Description: 0.082 miles of BOX BRIDGE & APPROACHES

Roadway Items:

MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF BRIDGE (STA.12+70)	1.000	UN
REMOVAL OF BROKEN CONCRETE	100.000	SY
REMOVE AND RELAY RIPRAP	150.000	SY
UNCLASSIFIED EXCAVATION (FM)	1,080.000	CY
CHANNEL EXCAVATION (FM)	350.000	CY
EXCESS EXCAVATION (FM)	760.000	CY
STRUCTURE EXCAVATION	500.000	CY
GEOTEXTILE FABRIC STABILIZATION (NON-WOVEN) (TYPE III) (AOS < 0.43 mm)	400.000	SY
TEMPORARY STREAM DIVERSION	1.000	EA
GRANULAR MATERIAL (CLASS 4, GROUP "C")	567.000	TON
CRUSHED STONE (SIZE 57)	270.000	TON
18" REINFORCED CONCRETE PIPE, CLASS III	32.000	LF
RIGHT-OF-WAY MARKERS (TYPE 1)	14.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF

EROSION CONTROL ITEMS:

COMMERCIAL FERTILIZER (13:13:13)	0.850	TON
AMMONIUM NITRATE	0.090	TON
SEEDING	0.850	AC
VEGETATIVE MATERIALS FOR MULCH	2.550	TON
EXCELSIOR BLANKET	1,750.000	SY
TEMPORARY SILT FENCE (TYPE I) (AOS 0.15 mm - 0.84 mm)	300.000	LF
WATTLES, 20"	80.000	LF
LOOSE RIPRAP, 300 LB.	835.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, NON-WOVEN, AOS < 0.43 mm	630.000	SY

BOX BRIDGE ITEMS:

BOX BRIDGE CONCRETE, CLASS "BB"	248.970	CY
REINFORCEMENT	55,908.000	LB