



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS**

County	Panola
Project No.	LSBP-54(33)
Road Name.	Tocowa Road
	A.K.A Muggy Hill Road

BIDS RECEIVED: FRIDAY, DECEMBER 5, 2025 AT 10:30 AM IN THE PANOLA COUNTY COURTHOUSE AT BATESVILLE, MS

Project Description: 0.029 miles of BOX BRIDGE and APPROACHES

ROADWAY ITEMS:

MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF PRECAST BRIDGE @ STA. 49+43.00	1.000	UN
REMOVAL OF ASPHALT (ALL DEPTHS)	127.000	SY
UNCLASSIFIED EXCAVATION (F.M.)	956.000	CY
BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 9)	328.000	CY
STRUCTURE EXCAVATION	1,119.000	CY
GEOTEXTILE FABRIC STABILIZATION, TYPE III, NON-WOVEN, AOS < 0.43mm	474.000	SY
TEMPORARY STREAM DIVERSION	1.000	EA
CRUSHED STONE (SIZE 610)	133.000	TON
CRUSHED STONE (SIZE 57)	320.000	TON
RIGHT-OF-WAY MARKERS (TYPE II)	10.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF

EROSION CONTROL ITEMS:

COMMERCIAL FERTILIZER (13:13:13)	0.071	TON
SEEDING	0.188	AC
VEGETATIVE MATERIALS FOR MULCH	0.376	TON
EXCELSIOR BLANKET	666.000	SY
TEMPORARY SILT FENCE (TYPE I) (AOS 0.15mm - 0.84mm)	801.000	LF
WATTLES, 20"	40.000	LF
LOOSE RIPRAP, 300 LB.	294.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, NON-WOVEN, AOS < 0.43mm	465.000	SY

BOX BRIDGE ITEMS:

BOX BRIDGE CONCRETE, CLASS "BB"	322.000	CY
REINFORCEMENT	54,299.000	LB