



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS**

County Panola
Project No. LSBP-54(34)
Road Name. Anthony Road

BIDS RECEIVED: 10:00 AM Friday, June 19, 2026, in the Panola County Courthouse at Batesville, MS

Project Description: 0.08 miles of BOX BRIDGE and APPROACHES

ROADWAY ITEMS:

	QUANTITY	UNIT
MOBILIZATION	1.000	LS
Clearing and Grubbing	1.000	LS
Removal of Obstructions	1.000	LS
Removal of Steel Sub & Timber Deck Bridge (Sta. 6+51.65)	1.000	UN
Removal of Pipe, (All Sizes)	30.000	LF
Unclassified Excavation (FM)	1,133.000	CY
Borrow Excavation (Contractor-Furnished)(FME)(Class 9)	210.000	CY
Structure Excavation	1,119.000	CY
GEOTEXTILE FABRIC STABILIZATION (TYPE III Non-Woven) (AOS <0.43)	468.000	SY
Temporary Stream Diversion	1.000	EA
Crushed Stone, Size #57	311.000	TON
Crushed Stone, Size #610	505.000	TON
18" Reinforced Concrete Pipe, Class III	129.000	LF
18" Branch Connection (R.C.P. to Wingwall of Box)	1.000	EA
Right-of-Way Markers (Type II)	12.000	EA
Maintenance of Traffic	1.000	LS
Additional Construction Signs	0.000	SF

EROSION CONTROL ITEMS:

	QUANTITY	UNIT
Commercial Fertilizer (13 : 13 : 13)	0.220	TON
Seeding	0.580	AC
Vegetative Materials for Mulch	1.150	TON
Excelsior Blanket	619.000	SY
Temporary Silt Fence (Type II)(AOS 0.15-0.84)	1,251.000	LF
Wattles, 20"	120.000	LF
Loose Riprap, 300 LB	327.000	TON
Geotextile Under Riprap, Type V, Non-Woven, AOS < 0.43	518.000	SY

BRIDGE ITEMS:

	QUANTITY	UNIT
Box Bridge Concrete, Class "BB"	308.000	CY
Reinforcement	52,287.000	LB