



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS**

County	Panola
Project No.	LSBP-54(35)
Road Name.	Hentz Road

BIDS RECEIVED: MONDAY, OCTOBER 5, 2026 AT 11:00 AM IN THE COURTHOUSE AT BATESVILLE, MS

Project Description: 0.161 miles of BRIDGE and APPROACHES

ROADWAY ITEMS:

	QUANTITY	UNIT
Mobilization	1.000	LS
Clearing and Grubbing	1.000	LS
Removal of Obstructions	1.000	LS
Removal of Precast Bridge @ Sta. 6+43.06	1.000	UN
Unclassified Excavation (F.M.)	334.000	CY
Borrow Excavation (Contractor-Furnished FME, Class 9)	1,168.000	CY
Crushed Stone, Size #610	975.000	TON
18" Reinforced Concrete Pipe, Class III	40.000	LF
Right-Of-Way Markers (Type II)	12.000	EA
Maintenance Of Traffic	1.000	LS
Additional Construction Signs	0.000	SF
Reflectorized Traffic Object Marker (Encap. Lens) (Type 3)	4.000	EA
Geotextile Under Bridge End Treatment, Type V, AOS <0.43, Non-Woven	248.000	SY

EROSION CONTROL ITEMS:

	QUANTITY	UNIT
Commercial Fertilizer (13 : 13 : 13)	0.500	TON
Seeding	1.330	AC
Vegetative Materials for Mulch	2.670	TON
Temporary Silt Fence (Type II) (AOS 0.15-0.84)	2,044.000	LF
Wattles, 20"	360.000	LF
Loose Riprap (300 lb.)	604.000	TON
Geotextile under Riprap, Type V, AOS <0.43, Non-Woven	959.000	SY

BRIDGE ITEMS:

	QUANTITY	UNIT
Test Piles, 18", Concrete	2.000	EA
Conventional Static Pile Load Test	0.000	EA
18" Prestressed Concrete Piling	680.000	LF
24" Pre-formed Pile Hole	200.000	LF
Bridge Concrete, Class "AA"	55.430	CY
Reinforcement	10,413.000	LB
31' Precast Concrete Slab Unit, 3.5' Interior	8.000	EA
31' Precast Concrete Slab Unit, 4.5' Interior	4.000	EA
40' Precast Concrete Slab Unit, 3.5' Interior	4.000	EA
40' Precast Concrete Slab Unit, 4.5' Interior	2.000	EA

31' Precast Concrete Slab Unit, 3.5' Exterior	4.000	EA
40' Precast Concrete Slab Unit, 3.5' Exterior	2.000	EA
Precast Concrete Barrier Rail	204.000	LF
Loose Riprap (300 lb.)	210.000	TON
Geotextile under Riprap, Type V, AOS <0.43, Non-Woven	334.000	SY