



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS**

County Pearl River
Project No. LSBP-55(39)
Road Name. Edmund Jones Road

BIDS RECEIVED: TUESDAY, JUNE 23, 2026 AT 10:00 AM IN THE BOARDROOM AT POPLARVILLE, MS

Project Description: 0.064 miles of BRIDGE and APPROACHES

ROADWAY ITEMS:

Mobilization	1.000	LS
Clearing and Grubbing	1.000	LS
Removal of Precast Bridge at Station 10+65	1.000	UN
Removal of Pavement	430.000	SY
Unclassified Excavation (FM)	110.000	CY
Channel Excavation (FM)	275.000	CY
Excess Excavation (FM)	55.000	CY
Granular Material LVM, (Class 6, Group C)	350.000	CY
Crushed Stone 610	300.000	TON
Right-of-Way Markers (Type I)	6.000	EA
Maintenance of Traffic	1.000	LS
Additional Construction Signs	0.000	SF
Reflectorized Traffic Object Marker (Encapsulated Lens) (Type 3)	4.000	EA

EROSION CONTROL ITEMS:

Agricultural Limestone	1.000	TON
Commercial Fertilizer (13-13-13)	0.500	TON
Seeding	0.500	AC
Vegetative Materials for Mulch	1.500	TON
Solid Sodding	200.000	SY
Temporary Silt Fence (Type II) (AOS 0.15-0.84)	750.000	LF
Erosion Mat	98.000	SY
Wattles, 20"	100.000	LF
Loose Riprap, 200 Lb.	100.000	TON
Geotextile under Bridge Abutment Non-Woven, Type V, AOS < 0.43	100.000	SY
Geotextile under Riprap Non-Woven, Type V, AOS < 0.43	200.000	SY

BRIDGE ITEMS:

Test Pile, 14" Prestressed Concrete	2.000	EA
Conventional Static Pile Load Test	0.000	EA
14" Prestressed Concrete Piling	1,060.000	LF
18" Pre-formed Pile Hole	220.000	LF
31' Precast Concrete Slab Unit, 3'-6" Interior, 30° Skew, Right Fwd.	30.000	EA
31' Precast Concrete Slab Unit, Curb, 30° Skew, Right Fwd.	10.000	EA

Beam-Type Railing with Concrete and Steel Posts	310.000	LF
33'-6" Precast Concrete Cap, Intermediate Unit, Concrete Pile, 30° Skew, Right Fwd.	4.000	EA
33'-6" Precast Concrete Cap, End Unit, Concrete Pile, 30° Skew, Right Fwd.	2.000	EA
9.33' Precast Concrete Wing	4.000	EA
Loose Riprap, 300 Lb.	203.000	TON
Geotextile under Riprap Non-Woven, Type V, AOS < 0.43	483.000	SY