



OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)

AND

COUNTY BOARD OF SUPERVISORS

County Pearl River

Project No. LSBP-55(40)

Road Name. S VALLEY ROAD

BIDS RECEIVED: TUESDAY, JUNE 17, 2025 AT 11:00 AM IN THE BOARDROOM AT POPLARVILLE, MS

Project Description: 0.132 miles of BRIDGE & APPROACHES

Roadway Items:

MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF PRECAST BRIDGE AT STATION 12+01	1.000	UN
UNCLASSIFIED EXCAVATION (FM)	605.000	CY
BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 7)	245.000	CY
BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 7)	2,160.000	CY
CHANNEL EXCAVATION (FM)	400.000	CY
GRANULAR MATERIAL (LVM), (CLASS 6, GROUP C)	845.000	CY
GRANULAR MATERIAL (LVM), (CLASS 6, GROUP C)	530.000	CY
CRUSHED STONE, 610	250.000	TON
CRUSHED STONE, 610	150.000	TON
RIGHT-OF-WAY MARKERS (TYPE I)	8.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	4.000	EA

EROSION CONTROL ITEMS:

AGRICULTURAL LIMESTONE	3.000	TON
COMMERCIAL FERTILIZER (13-13-13)	1.500	TON
SEEDING	1.500	AC
VEGETATIVE MATERIALS FOR MULCH	4.500	TON
SOLID SODDING	441.000	SY
EROSION MAT	320.000	SY
TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84)	1,500.000	LF
WATTLES, 20"	150.000	LF
LOOSE RIPRAP, 200 LB.	100.000	TON
GEOTEXTILE UNDER BRIDGE ABUTMENT NON-WOVEN, TYPE V, AOS < 0.43	100.000	SY
GEOTEXTILE UNDER RIPRAP NON-WOVEN, TYPE V, AOS < 0.43	200.000	SY

BRIDGE ITEMS:

TEST PILE	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
14" PRESTRESSED CONCRETE PILING	1,060.000	LF
18" PRE-FORMED PILE HOLE	220.000	LF
31' PRECAST CONCRETE SLAB UNIT, 3'-6" INTERIOR, 30 DEG SKEW, RT FWD	30.000	EA
31' PRECAST CONCRETE SLAB UNIT, CURB, 30 DEG SKEW, RT FWD	10.000	EA

BEAM TYPE RAILING WITH CONCRETE POSTS	310.000	LF
33'-6" PRECAST CONCRETE CAP, INTERMEDIATE UNIT, CONCRETE PILE, 30 DEG SKEW, RT FWD	4.000	EA
33'-6" PRECAST CONCRETE CAP, END UNIT, CONCRETE PILE, 30 DEG SKEW, RT FWD	2.000	EA
9.33' PRECAST CONCRETE WING	4.000	EA
LOOSE RIPRAP, 300 LB.	187.000	TON
GEOTEXTILE UNDER RIPRAP NON-WOVEN, TYPE V, AOS < 0.43	480.000	SY