



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS**

County Perry
Project No. LSBP-56(12)
Road Name. Site "A" & Site "B"

BIDS RECEIVED: TUESDAY, JULY 21, 2026 AT 10:00 AM IN THE BOARDROOM AT NEW AUGUSTA, MS

Project Description: 0.302 miles of BRIDGE and APPROACHES

<u>ROADWAY ITEMS:</u>	QUANTITY	UNIT
Mobilization	1.000	LS
Clearing and Grubbing	1.000	LS
Removal of Precast Bridge at Station 15+17	1.000	UN
Removal of Pavement	2,820.000	SY
Removal of Pipe (All Sizes)	320.000	LF
Unclassified Excavation (FM)	1,390.000	CY
Borrow Excavation (Contractor-Furnished FME, Class 9-8)	1,310.000	CY
Channel Excavation (FM)	2,220.000	CY
Structure Excavation	130.000	CY
Granular Material LVM, (Class 5, Group B)	2,945.000	CY
Crushed Stone 610	775.000	TON
Size II Stabilizer Aggregate, Coarse	50.000	CY
Class "B" Structural Concrete, Minor Structures	0.498	CY
18" Reinforced Concrete Pipe, Class III	72.000	LF
36" Reinforced Concrete Pipe, Class III	80.000	LF
18" Reinforced Concrete Pipe, End Section	4.000	EA
36" Reinforced Concrete Pipe, End Section	4.000	EA
Right-of-Way Markers (Type I)	26.000	EA
Maintenance of Traffic	1.000	LS
Additional Construction Signs	0.000	SF
Reflectorized Traffic Object Marker (Encapsulated Lens) (Type 3)	8.000	EA

<u>EROSION CONTROL ITEMS:</u>	QUANTITY	UNIT
Agricultural Limestone	5.000	TON
Commercial Fertilizer (13-13-13)	2.500	TON
Seeding	2.500	AC
Vegetative Materials for Mulch	7.500	TON
Solid Sodding	200.000	SY
Excelsior Blanket	700.000	SY
Temporary Silt Fence (Type II) (AOS 0.15-0.84)	3,300.000	LF
Wattles, 20"	660.000	LF
Loose Riprap, 200 Lb.	150.000	TON
Loose Riprap, 300 Lb.	75.000	TON
Geotextile under Bridge Abutment Non-Woven, Type V, AOS <0.43	200.000	SY

Geotextile under Riprap Non-Woven, Type V, AOS <0.43

300.000

SY

BRIDGE - SITE A ITEMS:

	QUANTITY	UNIT
Test Pile, 14" Prestressed Concrete	2.000	EA
Conventional Static Pile Load Test	0.000	EA
14" Prestressed Concrete Piling	590.000	LF
18" Preformed Pile Hole	180.000	LF
19' Precast Concrete Slab Unit, 3'-6" Interior, 30° Skew, Left Fwd.	6.000	EA
31' Precast Concrete Slab Unit, 3'-6" Interior, 30° Skew, Left Fwd.	18.000	EA
19' Precast Concrete Slab Unit, Curb, 30° Skew, Left Fwd.	2.000	EA
31' Precast Concrete Slab Unit, Curb, 30° Skew, Left Fwd.	6.000	EA
Beam-Type Railing with Concrete and Steel Posts	224.000	LF
33'-6" Precast Concrete Cap, Intermediate Unit, Concrete Pile, 30° Skew, Left Fwd.	3.000	EA
33'-6" Precast Concrete Cap, End Unit, Concrete Pile, 30° Skew, Left Fwd.	2.000	EA
9.33' Precast Concrete Wing	4.000	EA
Loose Riprap, 300 Lb.	87.000	TON
Geotextile under Riprap Non-Woven, Type V, AOS <0.43	232.000	SY

BRIDGE - SITE B ITEMS:

	QUANTITY	UNIT
Test Pile, 14" Prestressed Concrete	2.000	EA
Conventional Static Pile Load Test	0.000	EA
14" Prestressed Concrete Piling	590.000	LF
18" Preformed Pile Hole	180.000	LF
19' Precast Concrete Slab Unit, 3'-6" Interior	6.000	EA
31' Precast Concrete Slab Unit, 3'-6" Interior	18.000	EA
19' Precast Concrete Slab Unit, Curb	2.000	EA
31' Precast Concrete Slab Unit, Curb	6.000	EA
Beam-Type Railing with Concrete and Steel Posts	224.000	LF
29' Precast Concrete Cap, Intermediate Unit, Concrete Pile	3.000	EA
29' Precast Concrete Cap, End Unit, Concrete Pile	2.000	EA
7.5' Precast Concrete Wing	4.000	EA
Loose Riprap, 300 Lb.	86.000	TON
Geotextile under Riprap Non-Woven, Type V, AOS <0.43	190.000	SY