



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS**

County Perry
Project No. LSBP-56(13)
Road Name. Industrial Parkway

BIDS RECEIVED: TUESDAY, JULY 28, 2026 AT 10:00 AM IN THE BOARDROOM AT NEW AUGUSTA, MS

Project Description: 0.089 miles of BRIDGE and APPROACHES

ROADWAY ITEMS:

	QUANTITY	UNIT
Mobilization	1.000	LS
Clearing and Grubbing	1.000	LS
Unclassified Excavation (FM)	350.000	CY
Channel Excavation (FM)	1,960.000	CY
Excess Excavation (FM)	265.000	CY
Crushed Stone 610	800.000	TON
Right-of-Way Markers (Type I)	6.000	EA
Maintenance of Traffic	1.000	LS
Additional Construction Signs	0.000	SF
Reflectorized Traffic Object Marker (Encapsulated Lens) (Type 3)	4.000	EA

EROSION CONTROL ITEMS:

	QUANTITY	UNIT
Agricultural Limestone	2.000	TON
Commercial Fertilizer (13-13-13)	1.000	TON
Seeding	1.000	AC
Vegetative Materials for Mulch	3.000	TON
Solid Sodding	200.000	SY
Temporary Silt Fence (Type II) (AOS 0.15-0.84)	950.000	LF
Erosion Mat	380.000	SY
Wattles, 20"	200.000	LF
Loose Riprap, 200 Lb.	100.000	TON
Geotextile under Bridge Abutment Non-Woven, Type V, AOS <0.43	100.000	SY
Geotextile under Riprap Non-Woven, Type V, AOS <0.43	200.000	SY

BRIDGE ITEMS:

	QUANTITY	UNIT
Test Pile, 14" Prestressed Concrete	2.000	EA
Conventional Static Pile Load Test	0.000	EA
14" Prestressed Concrete Piling	2,070.000	LF
18" Preformed Pile Hole	480.000	LF
Bridge Concrete, Class "AA"	229.490	CY
40' Prestressed Concrete Beam, Type 1+2	397.500	LF
60' Prestressed Concrete Beam, Type III	597.500	LF
Reinforcement	40,269.000	LB
Concrete Railing	400.000	LF

Loose Riprap, 300 Lb.

664.000

TON

Geotextile under Riprap Non-Woven, Type V, AOS <0.43

1,662.000

SY