OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS

County Quitman
Project No. LSBP-60(16)
Road Name. ARMSTEAD-JONES RD.

BIDS RECEIVED: TUESDAY, DECEMBER 15, 2026 AT 1:00 PM IN THE COURTHOUSE AT MARKS, MS
Project Description: 0.073 miles of BOX BRIDGE & APPROACHES

Roadway Items:

MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF PIPE (ALL SIZES)	230.000	LF
UNCLASSIFIED EXCAVATION (FM)	694.000	CY
BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 9)	162.000	CY
CHANNEL EXCAVATION (FM)	276.000	CY
STRUCTURE EXCAVATION	308.000	CY
TEMPORARY STREAM DIVERSION	1.000	EA
GRANULAR MATERIAL, (CLASS 4, GROUP B)	593.000	TON
CRUSHED STONE , SIZE 57	200.000	TON
CLASS "B" STRUCTURAL CONCRETE, MINOR STRUCTURES	0.668	CY
18" REINFORCED CONCRETE PIPE, CLASS III	184.000	LF
48 " REINFORCED CONCRETE PIPE, CLASS III	56.000	LF
18 " REINFORCED CONCRETE PIPE, END SECTION	3.000	EA
48" REINFORCED CONCRETE PIPE, END SECTION	1.000	EA
ROADWAY CONSTRUCTION SURVEYING	1.000	LS
RIGHT-OF-WAY MARKERS (TYPE II)	8.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF

EROSION CONTROL ITEMS:

AGRICULTURAL LIMESTONE	1.240	TON
COMMERCIAL FERTILIZER (13:13:13)	0.620	TON
AMMONIUM NITRATE	0.060	TON
SEEDING	0.620	AC
VEGETATIVE MATERIALS FOR MULCH	1.860	TON
EXCELSIOR BLANKET	1,500.000	SY
TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84)	500.000	LF
WATTLES, 20"	300.000	LF
LOOSE RIPRAP, 300 LB.	320.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, NON-WOVEN AOS<0.43	860.000	SY

BOX BRIDGE ITEMS:

BOX BRIDGE CONCRETE, CLASS BB	140.620	CY
REINFORCEMENT	28,057.000	LB