



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS**

County Rankin

Project No. LSBP-61(7)

Road Name. Myers Road

BIDS RECEIVED: FRIDAY, MAY 8, 2026 AT 10:00 AM IN THE BOARDROOM AT BRANDON, MS

Project Description: 0.057 miles of BRIDGE and APPROACHES

ROADWAY ITEMS:

MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF PRECAST BRIDGE @ STA. 3+63.15	1.000	EA
REMOVAL OF ASPHALT PAVEMENT (ALL DEPTHS)	300.000	SY
UNCLASSIFIED EXCAVATION (FM)	563.000	CY
BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 9)	100.000	CY
EXCESS EXCAVATION (FM)	908.000	CY
CRUSHED STONE SIZE 610, (LVM)	225.000	CY
RIGHT-OF-WAY MARKERS (TYPE 1)	4.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	4.000	EA

EROSION CONTROL ITEMS:

AGRICULTURAL LIMESTONE	1.000	TON
COMMERCIAL FERTILIZER (13-13-13)	2.000	TON
AMMONIUM NITRATE	0.100	TON
SEEDING	1.000	AC
VEGETATIVE MATERIALS FOR MULCH	2.000	TON
SOLID SODDING	150.000	SY
TEMPORARY SILT FENCE (TYPE 1) (AOS 0.15-0.84)	800.000	LF
WATTLES, 20"	300.000	LF
LOOSE RIPRAP, 300 LB.	125.000	TON
GEOTEXTILE FABRIC UNDER RIPRAP, TYPE V, AOS < 0.43, NON-WOVEN	231.000	SY

BRIDGE ITEMS:

TEST PILE	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
14 " PRESTRESSED CONCRETE PILING	520.000	LF
18" PRE-FORMED PILE HOLES	200.000	LF
31 ' PRECAST CONCRETE SLAB UNIT, 3.5 ' INTERIOR, 30 DEG. SKEW, LT. FWD.	18.000	EA
31 ' PRECAST CONCRETE SLAB UNIT, 3.5 ' EXTERIOR, 30 DEG. SKEW, LT. FWD.	6.000	EA
PRECAST CONCRETE BARRIER RAIL	186.000	LF
36.0' PRECAST CONCRETE CAP, INTERMEDIATE UNIT, CONCRETE PILE, 30 DEG. SKEW, LT. FWD.	2.000	EA

36.0' PRECAST CONCRETE CAP, END UNIT, CONCRETE PILE, 30 DEG. SKEW, LT. FWD.	2.000	EA
11.33' PRECAST CONCRETE WING	4.000	EA
LOOSE RIPRAP, 300 LB.	1,170.000	TON
GEOTEXTILE FABRIC UNDER RIPRAP, TYPE V, AOS < 0.43, NON-WOVEN	2,200.000	SY