



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS**

County	Rankin
Project No.	LSBP-61(8)
Road Name.	Old Hwy 80

BIDS RECEIVED: THURSDAY, AUGUST 20, 2026 AT 10:00 AM IN THE BOARDROOM AT BRANDON, MS

Project Description: 0.087 miles of BRIDGE and APPROACHES

ROADWAY ITEMS:

	QUANTITY	UNIT
MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF PRECAST BRIDGE @ 15+77.05	1.000	UN
REMOVAL OF ASPHALT PAVEMENTS (ALL DEPTHS)	800.000	SY
REMOVAL OF PIPE (ALL SIZES)	40.000	LF
UNCLASSIFIED EXCAVATION (FM)	765.000	CY
BORROW EXCAVATION (CONTRACTOR-FURNISHED FME, CLASS 9)	100.000	CY
EXCESS EXCAVATION (FM)	143.000	CY
CRUSHED STONE 610, (LVM)	360.000	CY
24" CORRUGATED POLYETHYLENE PIPE	40.000	LF
GUARDRAIL, W-BEAM, COMPLETE-IN-PLACE	50.000	LF
GUARDRAIL, BRIDGE END SECTION, TYPE "I", THRIE BEAM	4.000	EA
GUARDRAIL, TERMINAL END SECTION	4.000	EA
RIGHT-OF-WAY MARKERS (TYPE I)	6.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	4.000	EA

EROSION CONTROL ITEMS:

	QUANTITY	UNIT
AGRICULTURAL LIMESTONE	0.900	TON
COMMERCIAL FERTILIZER (13-13-13)	1.900	TON
AMMONIUM NITRATE	0.100	TON
SEEDING	0.900	AC
VEGETATIVE MATERIALS FOR MULCH	2.700	TON
SOLID SODDING	150.000	SY
TEMPORARY SILT FENCE (TYPE I) (AOS 0.15 - 0.84)	1,500.000	LF
WATTLES, 20"	300.000	LF
LOOSE RIPRAP, 300 LB.	125.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, AOS < 0.43, NON WOVEN	231.000	SY

BRIDGE ITEMS:

	QUANTITY	UNIT
TEST PILE, 14" CONCRETE	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
14" PRESTRESSED CONCRETE PILING	590.000	LF

18" PREFORMED PILE HOLE	200.000	LF
31' PRECAST CONCRETE SLAB UNIT, 3.5' INTERIOR	18.000	EA
31' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR	6.000	EA
PRECAST CONCRETE BARRIER RAIL	186.000	LF
31.0' PRECAST CONCRETE CAP, INTERMEDIATE UNIT, CONCRETE PILE	2.000	EA
31.0' PRECAST CONCRETE CAP, END UNIT, CONCRETE PILE	2.000	EA
9.25' PRECAST CONCRETE WING	4.000	EA
Loose Riprap, 300 LB.	974.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, AOS < 0.43, NON-WOVEN	1,800.000	SY