



OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)

AND

COUNTY BOARD OF SUPERVISORS

**County** Sharkey

**Project No.** LSBP-63(16)

**Road Name.** LINDSEY (DOWLING BAYOU) ROAD

**BIDS RECEIVED:** Friday, May 17, 2024 in the Board Room at Rolling Fork, MS @ 10:00 am

**Project Description:** 0.062 miles of BRIDGE & APPROACHES

**Roadway Items:**

MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF BRIDGE (11+71)	1.000	UN
REMOVAL OF ASPHALT PAVEMENT	183.000	SY
UNCLASSIFIED EXCAVATION (FM)	3.000	CY
BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 9 )	1,880.000	CY
CHANNEL EXCAVATION (FM)	29.000	CY
CRUSHED STONE, No. 825 B	318.000	TON
RIGHT-OF-WAY MARKERS (TYPE II )	4.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3 )	4.000	EA

**EROSION CONTROL ITEMS:**

AGRICULTURAL LIMESTONE	0.900	TON
COMMERCIAL FERTILIZER ( 13:13:13 )	0.450	TON
SEEDING	0.450	AC
VEGETATIVE MATERIALS FOR MULCH	1.350	TON
TEMPORARY SILT FENCE (TYPE II ) (AOS 0.15 - 0.84 )	625.000	LF
WATTLES, 20"	100.000	LF

**BRIDGE ITEMS:**

TEST PILE	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
14" PRESTRESSED CONCRETE PILING	1,010.000	LF
18" PRE-FORMED PILE HOLES	200.000	LF
19' PRECAST CONCRETE SLAB UNIT, 3.5' INTERIOR	8.000	EA
19' PRECAST CONCRETE SLAB UNIT, 4.5' INTERIOR	4.000	EA
31' PRECAST CONCRETE SLAB UNIT, 3.5' INTERIOR	4.000	EA
31' PRECAST CONCRETE SLAB UNIT, 4.5' INTERIOR	2.000	EA
19' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR	4.000	EA
31' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR	2.000	EA
PRECAST CONCRETE BARRIER RAIL	138.000	LF
33' PRECAST CONCRETE CAP, INTERMEDIATE UNIT, CONCRETE PILE	2.000	EA
33' PRECAST CONCRETE CAP, END UNIT, CONCRETE PILE	2.000	EA
9.25' PRECAST CONCRETE WING	4.000	EA
LOOSE RIPRAP, 300 LB.	129.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, NON-WOVEN, AOS < 0.43	263.000	SY