



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS**

County Simpson

Project No. LSBP-64(27)

Road Name. Highway 472

BIDS RECEIVED: FRIDAY, OCTOBER 16, 2026 AT 10:30 AM IN THE BOARDROOM AT MENDENHALL, MS

Project Description: 0.071 miles of BOX BRIDGE and APPROACHES

ROADWAY ITEMS:

	QUANTITY	UNIT
Mobilization	1.000	LS
Clearing and Grubbing	1.000	LS
Removal of Precast Bridge @ Sta. 102+00	1.000	LS
Removal of Exist. Pavement (All Depths)	626.000	SY
Unclassified Excavation (FM)	2,200.000	CY
Borrow Excavation (Contractor-Furnished FME, Class 9)	600.000	CY
Structure Excavation (F.M.)	1,400.000	CY
Temporary Stream Diversion	1.000	EA
Crushed Stone, Size No. 825	275.000	TON
Roadway Construction Surveying	1.000	LS
Right-of-Way Markers (Type 1)	12.000	EA
Maintenance of Traffic	1.000	LS
Additional Construction Signs	0.000	SF
Reflectorized Traffic Object Marker (Encapsulated Lens) (Type 3)	4.000	EA

EROSION CONTROL ITEMS:

	QUANTITY	UNIT
Agricultural Limestone	1.000	TON
Commercial Fertilizer (13-13-13)	0.500	TON
Ammonium Nitrate	0.050	TON
Seeding	0.500	AC
Vegetative Materials for Mulch	1.500	TON
Temporary Silt Fence (Type II) (AOS 0.15 - 0.84)	850.000	LF
Wattles, 20"	160.000	LF

BOX BRIDGE ITEMS:

	QUANTITY	UNIT
Box Bridge Concrete, Class "BB"	384.850	CY
Reinforcement	71,366.000	LB
Loose Riprap, 300 LB.	160.000	TON
Geotextile under Loose Riprap (Type V) (Non-Woven) (AOS < 0.43)	320.000	SY