



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS**

County	Stone
Project No.	LSBP-66(17)
Road Name.	Herschel Road

BIDS RECEIVED: MONDAY, OCTOBER 6, 2025 AT 10:00 AM IN THE BOARDROOM AT WIGGINS, MS

Project Description: 0.07 miles of BRIDGE and APPROACHES

ROADWAY ITEMS:

MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF BRIDGE (STA. 11+74)	1.000	UN
REMOVAL OF EXISTING PAVEMENT	570.000	SY
REMOVAL OF PIPE (ALL SIZES)	24.000	LF
UNCLASSIFIED EXCAVATION (FM)	253.000	CY
BORROW EXCAVATION (F.M.E., CONTRACTOR FURNISHED, CLASS 9-8)	510.000	CY
GRANULAR MATERIAL (LVM) (CL. 6, GP. C)	80.000	CY
CRUSHED STONE, 610	500.000	TON
15" REINFORCED CONCRETE PIPE, CLASS III	32.000	LF
RIGHT-OF-WAY MARKERS (TYPE I)	9.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	4.000	EA
GEOTEXTILE UNDER CRUSHED STONE (TYPE V) (NON-WOVEN) (AOS < 0.43)	152.000	SY

EROSION CONTROL ITEMS:

TOPSOIL FOR SLOPE TREATMENT (CONTRACTOR FURNISHED) (LVM)	200.000	CY
SOLID SODDING	500.000	SY
EXCELSIOR BLANKET	500.000	SY
HYDROSEEDING	0.450	AC
TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84)	785.000	LF
WATTLES, 20"	300.000	LF

BRIDGE ITEMS:

TEST PILE	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
14 " PRESTRESSED CONCRETE PILING	760.000	LF
18" PRE-FORMED PILE HOLE	382.000	LF
19 ' PRECAST CONCRETE SLAB UNIT, 3'-6" INTERIOR	12.000	EA
31 ' PRECAST CONCRETE SLAB UNIT, 3'-6" INTERIOR	6.000	EA
19 ' PRECAST CONCRETE SLAB UNIT, CURB	4.000	EA
31 ' PRECAST CONCRETE SLAB UNIT, CURB	2.000	EA
BEAM TYPE RAILING WITH CONCRETE POSTS	138.000	LF

29' PRECAST CONCRETE CAP, INTERMEDIATE UNIT, CONCRETE PILE	2.000	EA
29' PRECAST CONCRETE CAP, END UNIT, CONCRETE PILE	2.000	EA
7.5' PRECAST CONCRETE WING	4.000	EA
LOOSE RIPRAP, 300 LB.	165.000	TON
GEOTEXTILE UNDER RIPRAP (TYPE V) (NON-WOVEN) (AOS < 0.43)	300.000	SY