



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS**

County	Tate
Project No.	LSBP-69(20)
Road Name.	WYATTE-TYRO ROAD

BIDS RECEIVED: FRIDAY, NOVEMBER 7, 2025 AT 10:00 AM IN THE TATE CO. ADMIN BLDG AT SENATOBIA, MS

Project Description: 0.057 miles of BOX CULVERT and APPROACHES

ROADWAY ITEMS:

Mobilization	1.000	LS
Clearing and Grubbing	1.000	LS
Removal of Obstructions	1.000	LS
Removal of Bridge (STA. 12+50)	1.000	UN
Removal of Fence	365.000	LF
Removal of Pipe (All Sizes)	61.000	LF
Unclassified Excavation (FM)	1,062.000	CY
Borrow Excavation (Contractor-Furnished FME, Class 9)	983.000	CY
Structure Excavation	128.000	CY
Temporary Stream Diversion	1.000	EA
Granular Material, (Class 4, Group C)	390.000	TON
Class "B" Structural Concrete	206.740	CY
Class "B" Structural Concrete, Minor Structures	2.490	CY
Reinforcing Steel	34,428.000	LB
24" Reinforced Concrete Pipe, Class III	51.000	LF
48" Reinforced Concrete Pipe, Class III	149.000	LF
24" Reinforced Concrete Pipe, End Section	1.000	EA
48" Reinforced Concrete Pipe, End Section	2.000	EA
24" Branch Connection R.C.P Stubbed into Wingwall	1.000	EA
Right-of-Way Markers (TYPE I)	11.000	EA
Maintenance of Traffic	1.000	LS
Additional Construction Signs	0.000	SF

EROSION CONTROL ITEMS:

Commercial Fertilizer (13-13-13)	0.140	TON
Ammonium Nitrate	0.010	TON
Seeding	0.140	AC
Vegetative Materials for Mulch	0.420	TON
Temporary Silt Fence (Type I) (AOS 0.15 - 0.84)	465.000	LF
Wattles, 20"	100.000	LF
Loose Riprap, 300 LB.	361.000	TON
Geotextile under Riprap, Type V, Non-woven AOS < 0.43	479.000	SY