



OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)  
AND  
COUNTY BOARD OF SUPERVISORS

**County** Washington  
**Project No.** LSBP-76(30)  
**Road Name.** Baker Road

**BIDS RECEIVED:** THURSDAY, APRIL 24, 2025 AT 10:00 AM IN THE BOARDROOM AT GREENVILLE, MS  
**Project Description:** 0.028 miles of BRIDGE & APPROACHES

**Roadway Items:**

MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF PRECAST BRIDGE (10+19)	1.000	UN
UNCLASSIFIED EXCAVATION (FM)	5.000	CY
CHANNEL EXCAVATION (FM)	238.000	CY
EXCESS EXCAVATION (FM)	25.000	CY
CRUSHED STONE, 825 B	105.000	TON
RIGHT-OF-WAY MARKERS (TYPE II)	4.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	4.000	EA

**EROSION CONTROL ITEMS:**

AGRICULTURAL LIMESTONE	0.400	TON
COMMERCIAL FERTILIZER ( 13:13:13 )	0.200	TON
SEEDING	0.200	AC
VEGETATIVE MATERIALS FOR MULCH	0.600	TON
TEMPORARY SILT FENCE (TYPE II) (AOS 0.15 - 0.84 )	300.000	LF
WATTLES	100.000	LF

**BRIDGE ITEMS:**

TEST PILE	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
18 " PRESTRESSED CONCRETE PILING	1,010.000	LF
22" PRE-FORMED PILE HOLES	200.000	LF
BRIDGE CONCRETE, CLASS A REINFORCEMENT	48.000	CY
	8,560.000	LB
19 ' PRECAST CONCRETE SLAB UNIT, 3.5' INTERIOR	4.000	EA
19 ' PRECAST CONCRETE SLAB UNIT, 4.5 ' INTERIOR	2.000	EA
31 ' PRECAST CONCRETE SLAB UNIT, 3.5' INTERIOR	8.000	EA
31' PRECAST CONCRETE SLAB UNIT, 4.5' INTERIOR	4.000	EA
19 ' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR	2.000	EA
31' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR	4.000	EA
PRECAST CONCRETE BARRIER RAIL	162.000	LF
LOOSE RIPRAP, 300 LB.	154.000	TON
GEOTEXTILE FABRIC UNDER RIPRAP, TYPE V, NON-WOVEN, AOS < 0.43	305.000	SY