



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS**

County Washington
Project No. LSBP-76(32)
Road Name. WILLIAMS BAYOU ROAD

BIDS RECEIVED: THURSDAY, OCTOBER 22, 2026 AT 10:00 AM IN THE BOARDROOM AT GREENVILLE, MS

Project Description: 0.041 miles of BRIDGE and APPROACHES

ROADWAY ITEMS:

	QUANTITY	UNIT
Mobilization	1.000	LS
Clearing and Grubbing	1.000	LS
Removal of Precast Bridge @ STA. 10+40	1.000	UN
Unclassified Excavation (FM)	28.000	CY
Borrow Excavation (Contractor-Furnished FME, Class 9)	6.000	CY
Channel Excavation (FM)	552.000	CY
Crushed Stone No. 610	147.000	TON
Right of Way Markers (Type II)	4.000	EA
Maintenance of Traffic	1.000	LS
Additional Construction Signs	0.000	SF
Reflectorized Traffic Object Marker (Encapsulated Lens) (Type 3)	4.000	EA

EROSION CONTROL ITEMS:

	QUANTITY	UNIT
AGRICULTURAL LIMESTONE	0.500	TON
COMMERCIAL FERTILIZER (13:13:13)	0.250	TON
SEEDING	0.250	AC
VEGETATIVE MATERIALS FOR MULCH	0.750	TON
TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84)	270.000	LF
Wattles, 20"	100.000	LF

BRIDGE ITEMS:

	QUANTITY	UNIT
19' Precast Concrete Slab Unit, 3.5' Interior	8.000	EA
19' Precast Concrete Slab Unit, 4.5' Interior	4.000	EA
31' Precast Concrete Slab Unit, 3.5' Interior	12.000	EA
31' Precast Concrete Slab Unit, 4.5' Interior	6.000	EA
19' Precast Concrete Slab Unit, 3.5' Exterior	4.000	EA
31' Precast Concrete Slab Unit, 3.5' Exterior	6.000	EA
Precast Concrete Barrier Rail	262.000	LF
Loose Riprap, 300 LB	190.000	TON
Geotextile under Riprap, Type V, Non-Woven, AOS < 0.43	289.000	SY

CONCRETE PILES ITEMS:

	QUANTITY	UNIT
Test Pile, 18" Prestressed Concrete	2.000	EA
Conventional Static Pile Load Test	0.000	EA

18" Prestressed Concrete Piling	2,120.000	LF
22" Pre-formed Pile Hole	360.000	LF
Bridge Concrete, Class AA	76.000	CY
Reinforcement	13,669.000	LB

ALTERNATE BID - STEEL PILES ITEMS:

	QUANTITY	UNIT
Test Pile, 14" Steel	2.000	EA
Conventional Static Pile Load Test	0.000	EA
14" Steel Piling	2,181.000	LF
18" Pre-formed Pile Hole	360.000	LF
Bridge Concrete, Class AA	91.000	CY
Reinforcement	12,818.000	LB