



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS**

County Washington

Project No. LSBP-76(33)

Road Name. Collier Road

BIDS RECEIVED: Thursday, March 26, 2026 at 10:00am in the Boardroom at Greenville, MS

Project Description: 0.057 miles of BRIDGE and APPROACHES

ROADWAY ITEMS:

	QUANTITY	UNIT
Mobilization	1.000	LS
Clearing and Grubbing	1.000	LS
Removal of Precast Bridge @ Sta. 11+21.00	1.000	UN
Removal of Pavement	494.000	SY
Removal of Pipe (All Sizes)	150.000	LF
Unclassified Excavation (FM)	363.000	CY
Borrow Excavation (Contractor-Furnished FME, Class 9)	26.000	CY
Channel Excavation (FM)	296.000	CY
Crushed Stone 825 B	358.000	TON
24" Polymeric Coated Corrugated Metal Pipe, 14 Gauge, 2-2/3" Corrugation	40.000	LF
30" Polymeric Coated Corrugated Metal Pipe, 14 Gauge, 2-2/3" Corrugation	80.000	LF
Right-of-Way Markers (II)	4.000	EA
Maintenance of Traffic	1.000	LS
Additional Construction Signs	0.000	SF
Reflectorized Traffic Object Marker (Encapsulated Lens) (Type 3)	4.000	EA

EROSION CONTROL ITEMS:

	QUANTITY	UNIT
Agricultural Limestone	0.740	TON
Commercial Fertilizer (13:13:13)	0.370	TON
Seeding	0.370	AC
Vegetative Materials for Mulch	1.110	TON
Temporary Silt Fence (Type II) (AOS 0.15 - 0.84)	600.000	LF
Wattles, 20"	200.000	LF

BRIDGE ITEMS:

	QUANTITY	UNIT
Test Pile, 18", Concrete	2.000	EA
Conventional Static Pile Load Test	0.000	EA
18" Prestressed Concrete Piling	870.000	LF
22" Preformed Pile Hole	200.000	LF
Bridge Concrete, Class AA	48.000	CY
Reinforcement	8,560.000	LB
19' Precast Concrete Slab Unit, 3.5' Interior	8.000	EA
19' Precast Concrete Slab Unit, 4.5' Interior	4.000	EA
31' Precast Concrete Slab Unit, 3.5' Interior	4.000	EA

31' Precast Concrete Slab Unit, 4.5' Interior	2.000	EA
19' Precast Concrete Slab Unit, 3.5' Exterior	4.000	EA
31' Precast Concrete Slab Unit, 3.5' Exterior	2.000	EA
Precast Concrete Barrier Rail	138.000	LF
Loose Riprap, 300 LB	162.000	TON
Geotextile under Riprap, Type V, AOS < 0.43	325.000	SY