



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS**

County Washington

Project No. LSBP-76(34)

Road Name. Huntington Point Road

BIDS RECEIVED: TUESDAY, JANUARY 27, 2026 AT 10:00 AM IN THE BOARDROOM AT GREENVILLE, MS

Project Description: 0.076 miles of BRIDGE and APPROACHES

ROADWAY ITEMS:

	QUANTITY	UNIT
Mobilization	1.000	LS
Clearing and Grubbing	1.000	LS
Removal of Bridge Slabs	190.000	SY
Removal of Crushed Stone	190.000	SY
Removal of Asphalt Pavement	410.000	SY
Unclassified Excavation (FM)	34.000	CY
Borrow Excavation (Contractor-Furnished FME, Class 9)	325.000	CY
Channel Excavation (FM)	568.000	CY
Crushed Stone 825B	258.000	TON
Right-of-Way Markers (II)	4.000	EA
Maintenance of Traffic	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
Reflectorized Traffic Object Marker (Encapsulated Lens) (Type 3)	4.000	EA

EROSION CONTROL ITEMS:

	QUANTITY	UNIT
Agricultural Limestone	0.600	TON
Commercial Fertilizer (13:13:13)	0.300	TON
Seeding	0.300	AC
Vegetative Materials for Mulch	0.900	TON
Temporary Silt Fence (Type II) (AOS 0.15 - 0.84)	540.000	LF
Wattles, 20"	100.000	LF

BRIDGE ITEMS:

	QUANTITY	UNIT
Test Pile, 18" Concrete	2.000	EA
Conventional Static Pile Load Test	0.000	EA
18" Prestressed Concrete Piling	1,780.000	LF
22" Preformed Pile Hole	500.000	LF
Bridge Concrete, Class AA	81.000	CY
Reinforcement	14,539.000	LB
31' Precast Concrete Slab Unit, 3.5' Interior	24.000	EA
31' Precast Concrete Slab Unit, 4.5' Interior	12.000	EA
31' Precast Concrete Slab Unit, 3.5' Exterior	12.000	EA
Precast Concrete Barrier Rail	372.000	LF
Loose Riprap, 300 LB	243.000	TON

Geotextile under Riprap, Type V, Non-Woven, AOS < 0.43

475.000

SY