



OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)

AND

COUNTY BOARD OF SUPERVISORS

County Yalobusha

Project No. LSBP-81(21)

Road Name. WEST LEE STREET

BIDS RECEIVED: MONDAY, SEPTEMBER 15, 2025 AT 9:00 AM IN THE COURTHOUSE AT COFFEEVILLE, MS

Project Description: 0.022 miles of BRIDGE & APPROACHES

Roadway Items:

MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF PRECAST BRIDGE @ STA. 1+74	1.000	UN
REMOVE AND RELAY RIPRAP	65.000	SY
UNCLASSIFIED EXCAVATION (FM)	26.000	CY
EXCESS EXCAVATION (FM)	245.000	CY
CRUSHED STONE, SIZE 610	350.000	TON
ROADWAY CONSTRUCTION SURVEYING	1.000	LS
RIGHT-OF-WAY MARKERS (TYPE II)	4.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	4.000	EA

EROSION CONTROL ITEMS:

AGRICULTURAL LIMESTONE	0.400	TON
COMMERCIAL FERTILIZER (13:13:13)	0.200	TON
AMMONIUM NITRATE	0.020	TON
SEEDING	0.200	AC
VEGETATIVE MATERIALS FOR MULCH	0.600	TON
TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84)	200.000	LF
WATTLES, 12"	200.000	LF

BRIDGE ITEMS:

TEST PILE	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
14" PRESTRESSED CONCRETE PILING	920.000	LF
18" PRE-FORMED PILE HOLES	460.000	LF
19' PRECAST CONCRETE SLAB UNIT, 3.5 ' INTERIOR, 30 DEG SKEW, LT. FWD	12.000	EA
40' PRECAST CONCRETE SLAB UNIT, 3.5 ' INTERIOR, 30 DEG SKEW, LT. FWD	6.000	EA
19' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR, 30 DEG SKEW, LT. FWD	4.000	EA
40' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR, 30 DEG SKEW, LT. FWD	2.000	EA
PRECAST CONCRETE BARRIER RAIL	156.000	LF
36.17' PRECAST CONCRETE CAP, INTERMEDIATE UNIT, CONCRETE PILE, 30 DEG SKEW, LT. FWD.	2.000	EA
36' PRECAST CONCRETE CAP, END UNIT, CONCRETE PILE, 30 DEG SKEW, LT. FWD.	2.000	EA
11.33' PRECAST CONCRETE WING	4.000	EA