



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS**

County	Yazoo
Project No.	LSBP-82(24)
Road Name.	Pritchard Avenue

BIDS RECEIVED: FRIDAY, NOVEMBER 6, 2026 AT 10:00 AM IN THE BOARDROOM AT YAZOO CITY, MS

Project Description: 0.155 miles of BRIDGE and APPROACHES

ROADWAY ITEMS:

MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF BRIDGE @ STA. 140+55	1.000	UNIT
REMOVAL OF ASPHALT PAVEMENT (ALL DEPTHS)	2,100.000	SY
REMOVAL OF CONCRETE PAVEMENT (ALL DEPTHS)	364.000	SY
REMOVAL OF PIPE (ALL SIZES)	75.000	LF
UNCLASSIFIED EXCAVATION (FM)	3,400.000	CY
BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 9)	662.000	CY
CRUSHED STONE SIZE 610 (FM)	1,250.000	TON
48 " REINFORCED CONCRETE PIPE, CLASS III	120.000	LF
48" REINFORCED CONCRETE PIPE, END SECTION	2.000	EACH
ROADWAY CONSTRUCTION SURVEYING	1.000	LS
BRIDGE CONSTRUCTION SURVEYING	1.000	LS
CONCRETE DRIVEWAY	364.000	SY
RIGHT-OF-WAY MARKERS (TYPE I)	6.000	EACH
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS)	4.000	EACH
STRUCTURE EXCAVATION	325.000	CY
HOT MIX ASPHALT (ST 9.5 MM)	215.000	TON
HOT MIX ASPHALT (ST 19 MM)	430.000	TON
4 " WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE) (90 MIL)	1,640.000	LF
4" WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW) (90 MIL)	1,640.000	LF
TWO-WAY CLEAR REFLECTIVE MARKERS	42.000	EACH
TWO-WAY YELLOW REFLECTIVE MARKERS	21.000	EACH

EROSION CONTROL ITEMS:

HYDROSEEDING	1.900	ACRE
TEMPORARY SILT FENCE (TYPE I) (AOS 0.15-0.84)	2,600.000	LF
WATTLES, 20"	160.000	LF
LOOSE RIPRAP, 100 LB.	75.000	TON

BRIDGE ITEMS:

TEST PILE	2.000	EA
-----------	-------	----

CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
14" PRESTRESSED CONCRETE PILING	1,890.000	LF
18 " PRE-FORMED PILE HOLES	100.000	LF
CONCRETE PILING CUT-OFF, 14 "	0.000	EA
BRIDGE CONCRETE, CLASS A	198.000	CY
40 ' PRESTRESSED CONCRETE BEAM TYPE I+2	397.500	LF
80 ' PRESTRESSED CONCRETE BEAM TYPE III	398.750	LF
REINFORCEMENT	34,988.000	LB
CONCRETE RAILING	320.000	LF
LOOSE RIPRAP, 300 LB.	1,830.000	TON