



OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)

AND

COUNTY BOARD OF SUPERVISORS

County Tippah
Project No. LSBP-70(30)
Road Name. COUNTY ROAD 738

BIDS RECEIVED: Monday, March 6, 2023 Ripley, MS @ 10:00a.m.

<u>ROADWAY ITEMS:</u>	QUANTITY	UNIT
MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF EXISTING BRIDGE AT STA. 96+85	1.000	UN
UNCLASSIFIED EXCAVATION (FM)	331.000	CY
BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 9)	1752.000	CY
SURPLUS EXCAVATION (FM)	340.000	CY
GEOTEXTILE FABRIC STABILIZATION (TYPE V) (AOS <0.43)	1540.000	SY
GRANULAR MATERIAL (FM OR LVM), (CLASS 5, GROUP C)	416.000	CY
36" REINFORCED CONCRETE PIPE, CLASS III	48.000	LF
65" X 48" REINFORCED CONCRETE ARCH PIPE,CLASS III	80.000	LF
65" X 48" REINFORCED CONCRETE ARCH PIPE, END SECTION	4.000	EA
RIGHT-OF-WAY MARKERS (TYPE II)	15.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	4.000	EA

<u>EROSION CONTROL ITEMS:</u>	QUANTITY	UNIT
WATTLES, 20"	300.000	LF
AGRICULTURAL LIMESTONE	1.260	TON
COMMERCIAL FERTILIZER (13-13-13)	0.630	TON
SEEDING	0.630	AC
SOLID SODDING	100.000	SY
EXCELSIOR BLANKET	2458.000	SY
TEMPORARY SILT FENCE (TYPE I OR II) (AOS 0.15-0.84)	1000.000	LF
LOOSE RIPRAP, 200 LB.	150.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, AOS <0.43	267.000	SY

<u>BRIDGE - STA. 96+61.93, 3@ 31' PRECAST CONCRETE SPAN BRIDGE, 28' CLEAR ROADWAY</u>	QUANTITY	UNIT
TEST PILE	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
18" PRESTRESSED CONCRETE PILING	520.000	LF
BRIDGE CONCRETE, CLASS "A"	45.180	CY
REINFORCEMENT	8024.000	LB
31' PRECAST CONCRETE SLAB UNIT, 3.5' INTERIOR	18.000	EA
31' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR	6.000	EA
PRECAST CONCRETE BARRIER RAIL	186.000	LF
LOOSE RIPRAP,300 LB.	162.000	TON

GEOTEXTILE UNDER RIPRAP, TYPE V NON-WOVEN, AOS <0.43

300.000

SY