



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS**

County Calhoun
Project No. SABP-07(01)
Road Name. CR 314

BIDS RECEIVED: MONDAY, MAY 4, 2026 AT 10:00 AM IN THE COURTHOUSE AT PITTSBORO, MS

Project Description: 0.083 miles of BOX BRIDGE and APPROACHES

ROADWAY ITEMS:

MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF CONCRETE BOX BRIDGE @ STA. 224+34	1.000	UN
UNCLASSIFIED EXCAVATION (FM)	631.000	CY
BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 9)	1,561.000	CY
CHANNEL EXCAVATION (FM)	1,728.000	CY
STRUCTURE EXCAVATION	3,351.000	CY
GEOTEXTILE FABRIC STABILIZATION, TYPE V, NON-WOVEN, AOS<0.43	1,712.000	SY
TEMPORARY STREAM DIVERSION	1.000	EA
CRUSHED STONE , SIZE 57	735.000	TON
CRUSHED STONE , SIZE 610	1,040.000	TON
HOT MIX ASPHALT, (ST) (12.5mm)	162.000	TON
FILTER MATERIAL FOR FILTER BEDS, TYPE B (Fill Sand)(PI=0)	1,500.000	TON
ROADWAY CONSTRUCTION SURVEYING	1.000	LS
RIGHT-OF-WAY MARKERS (TYPE II)	6.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF

EROSION CONTROL ITEMS:

AGRICULTURAL LIMESTONE	2.000	TON
COMMERCIAL FERTILIZER (13:13:13)	1.000	TON
AMMONIUM NITRATE	0.100	TON
SEEDING	1.000	AC
VEGETATIVE MATERIALS FOR MULCH	2.000	TON
EXCELSIOR BLANKET	100.000	SY
TEMPORARY SILT FENCE, TYPE II, AOS 0.15-0.84	1,000.000	LF
WATTLES, 12"	150.000	LF
LOOSE RIPRAP, 300 LB.	970.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, NON-WOVEN, AOS<0.43	2,775.000	SY

BRIDGE ITEMS:

BOX BRIDGE CONCRETE, CLASS BB	634.400	CY
REINFORCEMENT	156,175.000	LB

