



OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)

AND

COUNTY BOARD OF SUPERVISORS

County Carroll

Project No. SABP-08(01)

Road Name. COUNTY ROAD NO. 31

BIDS RECEIVED: MONDAY, JUNE 30, 2025 AT 10:00 AM IN THE COURTHOUSE AT VAIDEN, MS

Project Description: 0.25 miles of BOX BRIDGE & APPROACHES

Roadway Items:

MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF BRIDGE @ STA. 2+98 (SITE "A")	1.000	UN
REMOVAL OF BRIDGE @ STA. 3+37 (SITE "A")	1.000	UN
REMOVAL OF BRIDGE @ STA. 3+50 (SITE "B")	1.000	UN
REMOVE AND RELAY RIPRAP	540.000	SY
UNCLASSIFIED EXCAVATION (F.M.)	3,953.000	CY
BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 9)	146.000	CY
CHANNEL EXCAVATION (F.M.)	1,528.000	CY
EXCESS EXCAVATION (F.M.)	200.000	CY
STRUCTURE EXCAVATION	1,641.000	CY
TEMPORARY STREAM DIVERSION	2.000	EA
GRANULAR MATERIAL, (CL. 4, GP.B)	3,687.000	TON
CRUSHED STONE, SIZE 57	625.000	TON
SIZE 2 STABILIZER AGGREGATE, COARSE	451.000	TON
24" REINFORCED CONCRETE PIPE, CLASS III	80.000	LF
ROADWAY CONSTRUCTION SURVEYING	1.000	LS
RIGHT-OF-WAY MARKERS (TYPE II)	29.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF

EROSION CONTROL ITEMS:

AGRICULTURAL LIMESTONE	4.820	TON
COMMERCIAL FERTILIZER (13:13:13)	2.410	TON
AMMONIUM NITRATE	0.240	TON
SEEDING	2.410	AC
VEGETATIVE MATERIALS FOR MULCH	4.820	TON
EXCELSIOR BLANKET	1,340.000	SY
TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84)	1,200.000	LF
WATTLES, 12"	700.000	LF
LOOSE RIPRAP (300 LB.)	1,105.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, NON-WOVEN, AOS <0.43	3,265.000	SY

SITE "A" - BOX BRIDGE

BOX BRIDGE CONCRETE, CLASS BB	211.610	CY
REINFORCEMENT	40,405.000	LB

SITE "B" - BOX BRIDGE

BOX BRIDGE CONCRETE, CLASS BB
REINFORCEMENT

270.040	CY
52,027.000	LB