



OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)

AND

COUNTY BOARD OF SUPERVISORS

County Chickasaw
Project No. SABP-09(01)
Road Name. County Road 413 (Ira Cole Road)

BIDS RECEIVED: MONDAY, MAY 4, 2026 AT 10:00 AM IN THE BOARDROOM AT HOUSTON, MS

Project Description: 0.04 miles of BRIDGE & APPROACHES

Roadway Items:

MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF BRIDGE @ STA. 11+66	1.000	UN
REMOVAL OF PAVEMENT (ALL TYPES) (ALL DEPTHS)	237.000	SY
UNCLASSIFIED EXCAVATION (FM)	564.000	CY
EXCESS EXCAVATION (FM)	1,549.000	CY
GEOTEXTILE STABILIZATION (TYPE V) (AOS <0.43) (Non-Woven)	225.000	SY
GRANULAR MATERIAL (FM) (CLASS 5 GROUP "C")	6.000	CY
CRUSHED STONE (3/4" & DOWN) (FM)	83.000	CY
ASPHALT, ST, 9.5MM	50.000	TON
ASPHALT FOR TACK COAT (CBC-1H)	25.000	GAL
GUARD RAIL, "W" BEAM, STEEL POST	100.000	LF
GUARD RAIL, BRIDGE END SECTION, TYPE "I", "W" BEAM	4.000	EA
GUARD RAIL, TERMINAL END SECTION (DESIGNATION)	4.000	EA
RIGHT-OF-WAY MARKERS (TYPE I)	4.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
4" - WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE) (60 MILS)	0.077	MI
4" - WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW) (90 MILS)	406.000	LF
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	4.000	EA
REFLECTORIZED TRAFFIC DELINEATOR SIGN (ENCAPSULATED LENS)	12.000	EA

EROSION CONTROL ITEMS:

AGRICULTURAL LIMESTONE	0.060	TON
COMMERCIAL FERTILIZER (13-13-13)	0.060	TON
SEEDING	0.120	AC
VEGETATIVE MATERIALS FOR MULCH	0.240	TON
SOLID SODDING	100.000	SY
TEMPORARY SILT FENCE (TYPE I OR II) (AOS 0.15-0.84)	330.000	LF
WATTLES, 20"	30.000	LF

BRIDGE ITEMS:

TEST PILES, 14", STEEL	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
14" STEEL PILING	770.000	LF
18" PRE-FORMED PILE HOLES	200.000	LF

BRIDGE CONCRETE, CLASS "B"	9.040	CY
REINFORCEMENT	171.000	LB
31' PRECAST CONCRETE SLAB UNIT, 3.5' INTERIOR	12.000	EA
40' PRECAST CONCRETE SLAB UNIT, 3.5' INTERIOR	6.000	EA
31' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR	4.000	EA
40' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR	2.000	EA
PRECAST CONCRETE BARRIER RAIL	204.000	LF
31.33' PRECAST CONCRETE CAP, INT. UNIT, STEEL PILE	2.000	EA
31' PRECAST CONCRETE CAP, END UNIT, STEEL PILE	2.000	EA
9.25' PRECAST CONCRETE WING	4.000	EA
LOOSE RIPRAP, 300 LB.	1,998.000	TON
GEOTEXTILE UNDER RIPRAP,(TYPE V) (AOS <0.43) (Non-Woven)	2,959.000	SY