



OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)

AND

COUNTY BOARD OF SUPERVISORS

County Franklin

Project No. SABP-19(01)

Road Name. Davis Hill Road

BIDS RECEIVED: TUESDAY, NOVEMBER 25, 2025 AT 10:00 AM IN THE BOARDROOM AT MEADVILLE, MS

Project Description: 0.246 miles of BOX BRIDGE & APPROACHES

Roadway Items:

MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF BRIDGE AT STA. 138+88.92	1.000	UN
REMOVAL OF PAVEMENT (ALL TYPES)(ALL DEPTHS)	2,461.000	SY
REMOVAL OF PIPE (ALL SIZES)	65.000	LF
UNCLASSIFIED EXCAVATION (FM)	9,400.000	CY
BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 9)	655.000	CY
TEMPORARY STREAM DIVERSION	1.000	EA
GRANULAR MATERIAL (LVM), (CLASS 4, GROUP E)	1,629.000	CY
SIZE (II) STABILIZER AGGREGATE, COARSE	260.000	CY
24 " REINFORCED CONCRETE PIPE, CLASS III	64.000	LF
RIGHT-OF-WAY MARKERS (TYPE I)	18.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF

EROSION CONTROL ITEMS:

AGRICULTURAL LIMESTONE	8.200	TON
COMMERCIAL FERTILIZER (13-13-13)	1.230	TON
AMMONIUM NITRATE	0.410	TON
SEEDING	4.100	AC
VEGETATIVE MATERIALS FOR MULCH	8.200	TON
TEMPORARY GRASSING	4.100	AC
EXCELSIOR BLANKET	250.000	SY
EROSION MAT	870.000	SY
TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84)	1,500.000	LF
WATTLES, 12"	500.000	LF
WATTLES, 20"	500.000	LF
LOOSE RIPRAP, 100 LB.	455.000	TON
LOOSE RIPRAP, 300 LB.	280.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, AOS <0.43, NON-WOVEN	1,110.000	SY

BOX BRIDGE ITEMS:

BOX BRIDGE CONCRETE, CLASS BB	553.740	CY
REINFORCEMENT	139,740.000	LB