



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS**

County George

Project No. SABP-20(01)

Road Name. Broome School Rd.

BIDS RECEIVED: Thursday, October 22, 2026 at 10:00 am in the Boradroom at Lucedale, MS

Project Description: 0.085 miles of BOX CULVERT and APPROACHES

ROADWAY ITEMS:

MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
CLEARING AND GRUBBING	0.200	AC
REMOVAL OF OBSTRUCTIONS	1.000	LS
REMOVAL OF PRECAST BRIDGE (STA.129+06)	1.000	UN
REMOVAL OF ASPHALT (ALL DEPTHS)	900.000	SY
UNCLASSIFIED EXCAVATION (FM)	1,022.000	CY
BORROW EXCAVATION (CONTRACTOR FURNISHED LVM, CLASS 7)	4,317.000	CY
EXCESS EXCAVATION (LVM)	3,125.000	CY
TEMPORARY STREAM DIVERSION	2.000	EA
CRUSHED STONE (SIZE 57) (LVM)	115.000	CY
CRUSHED STONE (SIZE 610) (LVM)	374.000	CY
ASPHALT, TYPE ST, MIXTURE 9.5mm	242.000	TON
CLASS BB STRUCTURAL CONCRETE	133.020	CY
REINFORCING STEEL	23,944.000	LB
RIGHT-OF-WAY MARKERS (TYPE I)	11.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
4" WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE) (60 MILS)	0.170	MI
4" WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW) (90 MILS)	900.000	LF
TWO-WAY YELLOW REFLECTIVE HIGH PERFORMANCE RAISED MARKERS	11.000	EA

EROSION CONTROL ITEMS:

TOPSOIL FOR SLOPE TREATMENT (CONTRACTOR FURNISHED) (LVM)	600.000	CY
AGRICULTURAL LIMESTONE	2.000	TON
COMMERCIAL FERTILIZER (13-13-13)	1.000	TON
AMMONIUM NITRATE	0.500	TON
SEEDING	2.000	AC
VEGETATIVE MATERIALS FOR MULCH	2.000	TON
SOLID SODDING	1,000.000	SY
EXCELSIOR BLANKET	1,000.000	SY
TEMPORARY SILT FENCE (TYPE I) (AOS 0.15-0.84)	1,300.000	LF
WATTLES, 20"	150.000	LF
LOOSE RIPRAP, 200 LB.	100.000	TON

GEOTEXTILE UNDER RIPRAP, TYPE V, A.O.S. < 0.43, NON-WOVEN

185.000

SY