



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS**

County	Holmes
Project No.	SABP-26(01)
Road Name.	Lexington Road

BIDS RECEIVED: WEDNESDAY, JULY 16, 2025 AT 10:00 AM IN THE BOARDROOM AT LEXINGTON, MS

Project Description: 0.125 miles of BRIDGE and APPROACHES

ROADWAY ITEMS:

MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF BRIDGE @ STA. 12+77	1.000	UN
REMOVAL OF CULVERT @ STA. 12+33	1.000	UN
UNCLASSIFIED EXCAVATION (PM)	1,500.000	CY
SURPLUS EXCAVATION (FM)	370.000	CY
GRANULAR MATERIAL (LVM), (CLASS 4, GROUP B)	60.000	CY
HOT MIX ASPHALT, (ST) (12.5 MM)	135.000	TON
48" REINFORCED CONCRETE PIPE, CLASS I	40.000	LF
18" REINFORCED CONCRETE PIPE, CLASS I	76.000	LF
48" REINFORCED CONCRETE PIPE, END SECTION	1.000	EA
18" REINFORCED CONCRETE PIPE, END SECTION	2.000	EA
48" CORRUGATED POLYETHYLENE PIPE	80.000	LF
48" CORRUGATED POLYETHYLENE PIPE, END SECTION	1.000	EA
GUARD RAIL, W BEAM	323.000	LF
GUARD RAIL, BRIDGE END SECTION, TYPE I	4.000	EA
GUARD RAIL, TERMINAL END SECTION	4.000	EA
RIGHT-OF-WAY MARKERS (TYPE I)	12.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
4" WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE) (60 MIL)	0.250	MI
4" WIDE THERMOPLASTIC TRAFFIC STRIPE (SKIP YELLOW) (90 MIL)	0.125	MI
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	4.000	EA

EROSION CONTROL ITEMS:

AGRICULTURAL LIMESTONE	3.600	TON
COMMERCIAL FERTILIZER (13:13:13)	1.800	TON
AMMONIUM NITRATE	0.180	TON
SEEDING	1.800	AC
VEGETATIVE MATERIALS FOR MULCH	5.400	TON
TEMPORARY SILT FENCE (TYPE I) (AOS 0.15 - 0.84)	1,200.000	LF
WATTLES, 12"	100.000	LF

BRIDGE ITEMS:

TEST PILE	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
14 " PRESTRESSED CONCRETE PILING	1,270.000	LF
18" PRE-FORMED PILE HOLES	200.000	LF
BRIDGE CONCRETE, CLASS A	176.000	CY
40' PRESTRESSED CONCRETE BEAM TYPE I+2	318.000	LF
80' PRESTRESSED CONCRETE BEAM TYPE III	319.000	LF
REINFORCEMENT	36,136.000	LB
CONCRETE RAILING	320.000	LF
LOOSE RIPRAP, 300 LB.	500.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, AOS 0.21 - 0.43	550.000	SY