



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)  
AND  
COUNTY BOARD OF SUPERVISORS**

**County** Itawamba  
**Project No.** SABP-29(01)  
**Road Name.** Ozark Baptist Road

**BIDS RECEIVED:** MONDAY, MAY 18, 2026 AT 10:00 AM IN THE BOARDROOM AT FULTON, MS

**Project Description:** 0.056 miles of BOX CULVERT and APPROACHES

**ROADWAY ITEMS:**

MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF BRIDGE STA. 76+35	1.000	UN
UNCLASSIFIED EXCAVATION (FM)	559.000	CY
BORROW EXCAVATION (FME) (CONTRACTOR FURNISHED) (CLASS 9-6)	835.000	CY
EXCESS EXCAVATION (FM)	167.000	CY
GEOTEXTILE FABRIC STABILIZATION (TYPE V) (AOS <0.43)(NON-WOVEN)	1,267.000	SY
TEMPORARY STREAM DIVERSION	1.000	EA
GRANULAR MATERIAL (FM), (CLASS 5, GROUP "C")	30.000	CY
CRUSHED STONE (SIZE 3/4" & DOWN)(FM)	298.000	CY
HOT MIX ASPHALT, ST, 9.5 mm	123.000	TON
CLASS "B" STRUCTURAL CONCRETE	126.330	CY
REINFORCING STEEL	22,359.000	LB
24" CORRUGATED POLYETHYLENE PIPE	40.000	LF
RIGHT-OF-WAY MARKERS (TYPE II)	9.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
4" WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE) (60 MILS)	0.114	MI
4 " WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW) (90 MILS)	600.000	LF
TWO-WAY YELLOW REFLECTIVE HIGH PERFORMANCE RAISED MARKERS	10.000	EA

**EROSION CONTROL ITEMS:**

AGRICULTURAL LIMESTONE	1.440	TON
COMMERCIAL FERTILIZER (13-13-13)	0.720	TON
AMMONIUM NITRATE	0.180	TON
SEEDING	0.720	AC
SOLID SODDING	100.000	SY
EXCELSIOR BLANKET	3,505.000	SY
TEMPORARY SILT FENCE (TYPE I OR II) (AOS 0.15-0.84)	600.000	LF
WATTLES, 20"	100.000	LF
LOOSE RIPRAP, 300 LB.	172.000	TON
GEOTEXTILE UNDER RIPRAP (TYPE V)(NON-WOVEN)(AOS <0.43)	185.000	SY