



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS**

County	Jasper
Project No.	SABP-31(01)
Road Name.	CR 16

BIDS RECEIVED: MONDAY, NOVEMBER 2, 2026 AT 10:00 AM IN THE BOARDROOM AT BAY SPRINGS, MS

Project Description: 0.094 miles of BOX BRIDGE and APPROACHES REPLACE PC. CONC. BRIDGE W/ BOX BRIDGE

ROADWAY ITEMS:

Mobilization	1.000	LS
Clearing and Grubbing	1.000	LS
Removal of Precast Bridge @ Sta. 11+50.00	1.000	UN
Unclassified Excavation (FM)	977.000	CY
Borrow Excavation (Contractor Furnished, FME, Class 9)	430.000	CY
Channel Excavation (FM)	79.000	CY
Excess Excavation (FM)	252.000	CY
Temporary Stream Diversion	1.000	EA
Granular Material (LVM)(Class 9, Group B)	367.000	CY
Crushed Stone 825 (LVM)	15.000	CY
Asphalt, (ST), (19 mm)	167.000	TON
Asphalt, (ST), (9.5 mm)	92.000	TON
Filter Material for Filter Beds, Type C	306.000	CY
Roadway Construction Surveying	1.000	LS
Right-of-Way Markers (TYPE II)	12.000	EA
Maintenance of Traffic	1.000	LS
Additional Construction Signs	0.000	SF
4"-Wide Thermoplastic Edge Stripe (Continuous White) (90 MIL)	0.189	MI
4"-Wide Thermoplastic Traffic Stripe (Skip Yellow) (120 MIL)	0.095	MI
Two Way Yellow Reflective High Performance Raised Markers	13.000	EA
Reflectorized Traffic Object Marker (Encapsulated Lens) (Type 3)	4.000	EA

EROSION CONTROL ITEMS:

Agricultural Limestone	1.960	TON
Commercial Fertilizer (13:13:13)	0.980	TON
Ammonium Nitrate	0.098	TON
Seeding	0.980	AC
Vegetative Materials for Mulch	1.960	TON
Solid Sodding	110.000	SY
Temporary Silt Fence (Type II) (AOS 0.15 - 0.84)	1,300.000	LF
Wattles, 20"	380.000	LF
Loose Riprap, 100 LB	100.000	TON
Loose Riprap, 200 LB	44.000	TON
Geotextile under Riprap, Type V, AOS<0.43, NON-WOVEN	85.000	SY

BRIDGE ITEMS:

Box Bridge Concrete, Class "BB"
Reinforcement

202.900	CY
42,459.000	LB