



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)  
AND  
COUNTY BOARD OF SUPERVISORS**

**County** Jones  
**Project No.** SABP-34(01)  
**Road Name.** AUGUSTA ROAD

**BIDS RECEIVED:** FRIDAY, JUNE 19, 2026 AT 10:00 AM IN THE BOARDROOM AT LAUREL, MS

**Project Description:** 0.057 miles of BOX BRIDGE and APPROACHES

**ROADWAY ITEMS:**

	QUANTITY	UNIT
MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF PRECAST BRIDGE @ STA. 14+31.52	1.000	UN
UNCLASSIFIED EXCAVATION (FM)	2,184.000	CY
MUCK EXCAVATION (FM)	225.000	CY
BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 9)	2,896.000	CY
TEMPORARY STREAM DIVERSION	1.000	EA
CRUSHED STONE, (SIZE 825)	560.000	TON
HOT MIX ASPHALT, ST, 9.5mm	61.000	TON
HOT MIX ASPHALT, ST, 19mm	184.000	TON
FILTER MATERIAL FOR FILTER BEDS, TYPE "A"	405.000	TON
ROADWAY CONSTRUCTION SURVEYING	1.000	LS
RIGHT-OF-WAY MARKERS (TYPE II)	8.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
4" WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE) (60MIL)	0.114	MI
4" WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW) (90MIL)	600.000	LF
TWO-WAY YELLOW REFLECTIVE HIGH PERFORMANCE RAISED MARKERS	9.000	EA
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	4.000	EA

**EROSION CONTROL ITEMS:**

	QUANTITY	UNIT
AGRICULTURAL LIMESTONE	2.000	TON
COMMERCIAL FERTILIZER (13:13:13)	1.000	TON
SEEDING	1.000	AC
VEGETATIVE MATERIALS FOR MULCH	2.000	TON
SOLID SODDING	100.000	SY
TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84)	864.000	LF
WATTLES, 12"	300.000	LF
LOOSE RIPRAP, 100 LB.	50.000	TON
LOOSE RIPRAP, 200 LB.	239.000	TON
GEOTEXTILE UNDER RIPRAP, NON-WOVEN, TYPE V, AOS <0.43	534.000	SY

**BRIDGE ITEMS:**

	QUANTITY	UNIT
BOX BRIDGE CONCRETE, CLASS "BB"	268.740	CY

REINFORCEMENT

52,595.000

LB