



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)  
AND  
COUNTY BOARD OF SUPERVISORS**

|                    |                                            |
|--------------------|--------------------------------------------|
| <b>County</b>      | Lee                                        |
| <b>Project No.</b> | SABP-41(01)                                |
| <b>Road Name.</b>  | COUNTY ROAD 251 (SALTILLO- MUD CREEK ROAD) |

**BIDS RECEIVED:** Monday August 17, 2026 in the Board of Supervisors at Tupelo, MS at 8:00am

**Project Description:** 0.113 miles of BRIDGE and APPROACHES

**ROADWAY ITEMS:**

|                                                                    |           |     |
|--------------------------------------------------------------------|-----------|-----|
| Mobilization                                                       | 1.000     | LS  |
| Clearing and Grubbing                                              | 1.000     | LS  |
| Removal of Bridge at Sta. 20+70                                    | 1.000     | UN  |
| Removal of Pavement (All Thicknesses)                              | 1,169.000 | SY  |
| Unclassified Excavation (FM)                                       | 841.000   | CY  |
| Channel Excavation (FM)                                            | 842.000   | CY  |
| Geotextile Fabric Stabilization (Type V)(AOS <0.43)(Non-Woven)     | 2,600.000 | SY  |
| Granular Material (LVM)(Cl.5, Gp. C)                               | 128.000   | CY  |
| Crushed Stone (Size 3/4" & Down)(FM)                               | 925.000   | CY  |
| Mixing, Shaping, and Compaction                                    | 1,383.000 | SY  |
| Asphalt, ST, 9.5 mm                                                | 211.000   | TON |
| Asphalt for Prime Coat (MC-70 or EA-1)                             | 484.000   | GAL |
| Guardrail, "W" Beam                                                | 100.000   | LF  |
| Guardrail, Bridge End Section, Type "I" Thrie Beam                 | 4.000     | EA  |
| Guardrail, Terminal End Section                                    | 4.000     | EA  |
| Right-of-Way Markers (Type II)                                     | 7.000     | EA  |
| Maintenance of Traffic                                             | 1.000     | LS  |
| Additional Construction Signs                                      | 0.000     | SF  |
| 4" Wide Thermoplastic Edge Stripe (Continuous White) (60 mils)     | 0.227     | MI  |
| 4" Wide Thermoplastic Traffic Stripe (Continuous Yellow) (90 mils) | 1,200.000 | LF  |
| Two-Way Yellow Reflective High-Performance Raised Markers          | 8.000     | EA  |
| Reflectorized Traffic Object Marker (Encapsulated Lens) (Type 3)   | 4.000     | EA  |
| Reflectorized Traffic Delineator Sign (Encapsulated Lens)          | 14.000    | EA  |

**EROSION CONTROL ITEMS:**

|                                                    |           |     |
|----------------------------------------------------|-----------|-----|
| Agricultural Limestone                             | 2.500     | TON |
| Commercial Fertilizer (13-13-13)                   | 1.250     | TON |
| Seeding                                            | 1.250     | AC  |
| Vegetative Materials for Mulch                     | 2.500     | TON |
| Solid Sodding                                      | 100.000   | SY  |
| Temporary Silt Fence (Type I or II)(AOS 0.15-0.84) | 1,000.000 | LF  |
| Wattles, 20"                                       | 80.000    | LF  |

**BRIDGE ITEMS:**

|                                                       |            |     |
|-------------------------------------------------------|------------|-----|
| Test Pile                                             | 2.000      | EA  |
| Conventional Static Pile Load Test                    | 0.000      | EA  |
| 12" Steel Piling                                      | 1,350.000  | LF  |
| 18" Pre-formed Pile Hole                              | 1,089.000  | LF  |
| Bridge Concrete, Class A                              | 170.700    | CY  |
| 31' Prestressed Concrete Beam, Type I+2               | 307.500    | LF  |
| 60' Prestressed Concrete Beam, Type III               | 298.750    | LF  |
| Reinforcement                                         | 27,951.000 | LB  |
| Concrete Railing                                      | 244.000    | LF  |
| Loose Riprap, 300 lb.                                 | 875.000    | TON |
| Geotextile under Riprap, Type V, AOS <0.43, Non-woven | 775.000    | SY  |