



OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)

AND

COUNTY BOARD OF SUPERVISORS

County Leflore
Project No. SABP-42(01)
Road Name. COUNTY ROAD 507

BIDS RECEIVED: MONDAY, AUGUST 4, 2025 AT 3:00 PM IN THE BOARDROOM AT GREENWOOD, MS
Project Description: 0.309 miles of BRIDGE & APPROACHES

Roadway Items:

MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF OBSTRUCTIONS	1.000	LS
REMOVAL OF BRIDGE @ STA. 8+23	1.000	UN
REMOVAL OF PIPE (ALL SIZES)	150.000	LF
UNCLASSIFIED EXCAVATION (FM)	5,560.000	CY
BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 9)	330.000	CY
GRANULAR MATERIAL, (CLASS 4, GROUP B)	5,202.000	TON
SIZE (2) STABILIZER AGGREGATE, COARSE	645.000	TON
24" REINFORCED CONCRETE PIPE, CLASS III	136.000	LF
36 " REINFORCED CONCRETE PIPE, CLASS III	96.000	LF
GUARD RAIL, W-BEAM	75.000	LF
GUARD RAIL, BRIDGE END SECTION,TYPE "I"(THRIE BEAM)	4.000	EA
GUARD RAIL, TERMINAL END SECTION	4.000	EA
CONSTRUCTION SURVEYING	1.000	LS
RIGHT-OF-WAY MARKERS (TYPE II)	24.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	4.000	EA

EROSION CONTROL ITEMS:

AGRICULTURAL LIMESTONE	6.800	TON
COMMERCIAL FERTILIZER (13:13:13)	3.400	TON
AMMONIUM NITRATE	0.340	TON
SEEDING	3.400	AC
VEGETATIVE MATERIALS FOR MULCH	6.800	TON
EXCELSIOR BLANKET	1,860.000	SY
TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84)	400.000	LF
WATTLES, 12"	400.000	LF
LOOSE RIPRAP (300 LB.)	80.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, NON-WOVEN, AOS <0.43	145.000	SY

BRIDGE ITEMS:

TEST PILE	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
18 " PRESTRESSED CONCRETE PILING	1,890.000	LF

24 " PRE-FORMED PILE HOLES	200.000	LF
BRIDGE CONCRETE, CLASS A	170.000	CY
31 ' PRESTRESSED CONCRETE BEAM TYPE (1+2)	307.500	LF
40 ' PRESTRESSED CONCRETE BEAM TYPE (1+2)	198.750	LF
REINFORCEMENT	29,627.000	LB
CONCRETE RAILING	204.000	LF
LOOSE RIPRAP (300 LB.)	798.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V,NON-WOVEN, AOS <0.43	1,485.000	SY