



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS**

County	Lowndes
Project No.	SABP-44(01)
Road Name.	Old Macon Road

BIDS RECEIVED: Thursday, February 19, 2026 in the Supervisors Boardroom at Columbus, MS

Project Description: 0 miles of BRIDGE REPAIR

ROADWAY ITEMS:

MOBILIZATION	1.000	LS
REMOVAL OF HP 10X42 STEEL PILING	10.000	UN
REMOVAL OF 29'-6" PRECAST CONCRETE CAP, INTERMEDIATE UNIT, STEEL PILE	2.000	UN
REMOVE AND RELAY RIPRAP	174.000	SY
GRANULAR MATERIAL (LVM), (CLASS 3, GROUP B)	108.260	CY
SIZE I STABILIZER AGGREGATE, COARSE (LVM)	25.000	CY
BRIDGE CONSTRUCTION SURVEYING	1.000	LS
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	4.000	EA

EROSION CONTROL ITEMS:

AGRICULTURAL LIMESTONE	0.500	TON
COMMERCIAL FERTILIZER (13-13-13)	0.150	TON
SEEDING	0.500	AC
VEGETATIVE MATERIALS FOR MULCH	1.500	TON
TEMPORARY SILT FENCE (TYPE III) (AOS 0.15-0.84)	100.000	LF
WATTLES, 20"	100.000	LF

BRIDGE ITEMS:

TEST PILE	1.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
14" STEEL PILING	385.000	LF
BRIDGE CONCRETE, CLASS A	22.000	CY
REINFORCEMENT	2,630.000	LB
BEAM TYPE RAILING WITH CONCRETE POSTS	200.000	LF
19' PRECAST CONCRETE SLAB UNIT, 3'-6" INTERIOR (SALVAGE AND REINSTALLATION)	12.000	EA
31' PRECAST CONCRETE SLAB UNIT, 3'-6" INTERIOR (SALVAGE AND REINSTALLATION)	12.000	EA
19' PRECAST CONCRETE SLAB UNIT, CURB (SALVAGE AND REINSTALLATION)	4.000	EA
31' PRECAST CONCRETE SLAB UNIT, CURB (SALVAGE AND REINSTALLATION)	4.000	EA
LOOSE RIPRAP, 300 LB.	541.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, NON-WOVEN (AOS < 0.43)	795.000	SY