



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS**

County	Monroe
Project No.	SABP-48(01)
Road Name.	Liberty Road

BIDS RECEIVED: FRIDAY, OCTOBER 23, 2026 AT 9:00 AM IN THE CHANCERY CLERK BUILDING AT ABERDEEN, MS

Project Description: 0.189 miles of BRIDGE and APPROACHES

ROADWAY ITEMS:

	QUANTITY	UNIT
Mobilization	1.000	LS
Clearing and Grubbing	1.000	LS
Removal of Bridge @ Sta. 241+54	1.000	UN
Removal of Pavement (All Thicknesses)	5,209.000	SY
Unclassified Excavation (FM)	1,612.000	CY
Borrow Excavation (Contractor Furnished FME, Class 9-6)	2,180.000	CY
Geotextile Fabric Stabilization (Type V)(AOS <0.43)(NON-WOVEN)	4,397.000	SY
Granular Material (CLASS 5, GROUP "C") (LVM)	164.000	CY
Crushed Stone (SIZE 3/4" & DOWN) (FM)	881.000	CY
Asphalt, ST 9.5 MM	156.000	TON
Asphalt, ST 19 MM	260.000	TON
Asphalt for Prime Coat, (MC-70 OR EA-1)	662.000	GAL
Guardrail, "W" Beam	100.000	LF
Guardrail, Bridge End Section, Type "I" Thrie Beam	4.000	EA
Guardrail, Terminal End Section	4.000	EA
Maintenance of Traffic	1.000	LS
Additional Construction Signs	0.000	SF
4" Wide Thermoplastic Edge Stripe (Continuous White) (60 mils)	0.379	MI
4" Wide Thermoplastic Traffic Stripe (Continuous Yellow) (90 Mils)	2,000.000	LF
Two-Way Yellow Reflective High Performance Raised Markers	15.000	EA
Reflectorized Traffic Object Marker (Encapsulated Lens) (Type 3)	4.000	EA
Reflectorized Traffic Delineator Signs (Encapsulated Lens)	14.000	EA

EROSION CONTROL ITEMS:

	QUANTITY	UNIT
Agricultural Limestone	1.100	TON
Commercial Fertilizer (13-13-13)	0.550	TON
Ammonium Nitrate	0.280	TON
Seeding	1.160	AC
Solid Sodding	100.000	SY
Excelsior Blanket	5,000.000	SY
Temporary Silt Fence (Type I or II) (AOS 0.15-0.84)	2,200.000	LF
Turbidity Barrier	300.000	LF
Wattles, 20"	40.000	LF

BRIDGE ITEMS:

	QUANTITY	UNIT
Test Pile 14", Steel	2.000	EA
Conventional Static Pile Load Test	0.000	EA
14" Steel Piling	1,350.000	LF
18" Pre-formed Pile Hole	941.000	LF
Bridge Concrete, Class AA	227.000	CY
40 Ft. Prestressed Concrete Beam, Type I+2	397.500	LF
80 Ft. Prestressed Concrete Beam, Type III	398.750	LF
Reinforcement	36,986.000	LB
Concrete Railing	318.000	LF
Loose Riprap, 300 Lb.	1,193.000	TON
Geotextile under Riprap, Type V, AOS <0.43	1,060.000	SY