



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS**

County Pearl River

Project No. SABP-55(01)

Road Name. Holden Road

BIDS RECEIVED: Wednesday, December 17, 2025 at 10:00am in the Boardroom at Poplarville

Project Description: 0 miles of BRIDGE REPAIR

ROADWAY ITEMS:

	QUANTITY	UNIT
Mobilization	1.000	LS
Clearing and Grubbing	1.000	LS
Removal of Obstructions	1.000	LS
Crushed Stone, Size 610	50.000	TON
Maintenance of Traffic	1.000	LS
Additional Construction Signs	0.000	SF
Reflectorized Traffic Object Marker (Encapsulated Lens) (Type 3)	4.000	EA

BRIDGE ITEMS:

	QUANTITY	UNIT
Cleaning and Sealing Joints	192.000	LF
Class B Structural Concrete, Minor Structures	2.320	CY
Reinforcement	52.000	LB
Loose Riprap, 300 Lb.	300.000	TON
Geotextile under Riprap Non-Woven, Type V, AOS < 0.43	300.000	SY
Maintenance Painting of Metal Structure	1.000	LS
Polymer Cement Surface System	980.000	SY
General Epoxy Repair	20.000	SF