



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS**

County Quitman
Project No. SABP-60(01)
Road Name. Hood Road

BIDS RECEIVED: THURSDAY, APRIL 16, 2026 AT 9:00 AM IN THE BOARDROOM AT MARKS, MS

Project Description: 0.113 miles of BRIDGE and APPROACHES

ROADWAY ITEMS:

Mobilization	1.000	LS
Clearing and Grubbing	1.000	LS
Removal of Precast Bridge @ STA. 136+43	1.000	UN
Unclassified Excavation (F.M.)	735.000	CY
Excess Excavation (F.M.)	416.000	CY
Geotextile Fabric Stabilization, Type V, Non-woven, AOS <0.43	2,726.000	SY
Crushed Stone, Size 610	1,856.000	TON
Asphalt, ST, 12.5 mm	247.000	TON
Guardrail, W-Beam	75.000	LF
Guardrail, Bridge End Section, Type "I" (Thrie Beam)	4.000	EA
Guardrail, Terminal End Section	4.000	EA
Roadway Construction Surveying	1.000	LS
Maintenance of Traffic	1.000	LS
Additional Construction Signs	0.000	SF
4"-Wide Thermoplastic Edge Stripe (Continuous White) (90 Mils)	0.225	MI
4"-Wide Thermoplastic Traffic Stripe (Skip Yellow) (120 Mils)	0.100	MI
4"-Wide Thermoplastic Traffic Stripe (Continuous Yellow) (120 Mils)	664.000	LF
Two-Way Yellow Reflective High Performance Raised Markers	10.000	EA
Reflectorized Traffic Object Marker (Encapsulated Lens) (Type 3)	4.000	EA

EROSION CONTROL ITEMS:

Agricultural Limestone	1.560	TON
Commercial Fertilizer (13:13:13)	0.780	TON
Ammonium Nitrate	0.080	TON
Seeding	0.780	AC
Vegetative Materials for Mulch	1.560	TON
Excelsior Blanket	100.000	SY
Temporary Silt Fence (Type II) (AOS 0.15-0.84)	1,200.000	LF
Wattles, 12"	150.000	LF

BRIDGE ITEMS:

Test Pile, 14", Steel	2.000	EA
Conventional Static Pile Load Test	0.000	EA
14" Steel Piling	720.000	LF

18" Preformed Pile Hole	360.000	LF
Bridge Concrete, Class "A"	53.000	CY
Reinforcement	8,124.000	LB
19' Precast Concrete Slab Unit, 3.5' Interior	12.000	EA
31' Precast Concrete Slab Unit, 3.5' Interior	6.000	EA
19' Precast Concrete Slab Unit, 3.5' Exterior	4.000	EA
19' Precast Concrete Slab Unit, 3.5' Exterior	2.000	EA
Precast Concrete Barrier Rail	138.000	LF
Loose Riprap (300 lb.)	303.000	TON
Geotextile under RipRap, Type V, Non-woven, AOS <0.43	568.000	SY