



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS**

County Tippah
Project No. SABP-70(01)
Road Name. Gunn Road (CR 116)

BIDS RECEIVED: THURSDAY, AUGUST 6, 2026 AT 10:00 AM IN THE BOARDROOM AT CORINTH, MS

Project Description: 0.108 miles of BOX CULVERT and APPROACHES

ROADWAY ITEMS:

	QUANTITY	UNIT
Mobilization	1.000	LS
Clearing and Grubbing	1.000	LS
Removal of Existing Bridge at Sta. 77+89.41	1.000	UN
Unclassified Excavation (FM)	1,919.000	CY
Borrow Excavation (Contractor-Furnished FME, Class 9)	57.000	CY
Excess Excavation (LVM)	1,160.000	CY
Geotextile Fabric Stabilization (Type V, Non-woven)(AOS <0.43)	2,192.000	SY
Temporary Stream Diversion	1.000	EA
Granular Material (LVM), (Class 5, Group C)	123.000	CY
Crushed Stone (size 3/4" & down)(FM)	550.000	CY
Asphalt, ST, 9.5mm	228.000	TON
Asphalt for Prime Coat, Grade (MC-70 or EA-1)	528.000	GAL
Class B Structural Concrete	248.960	CY
Reinforcing Steel	55,514.000	LB
18" Corrugated Polyethylene Pipe	80.000	LF
Right-of-Way Markers (Type II)	16.000	EA
Maintenance of Traffic	1.000	LS
Additional Construction Signs	0.000	SF
4" - Wide Thermoplastic Edge Stripe (Continuous White) (60 mil)	0.216	MI
4" - Wide Thermoplastic Traffic Stripe (Continuous Yellow) (90 mil)	1,140.000	LF
Two-Way Yellow Reflective High Performance Raised Markers	13.000	EA
Reflectorized Traffic Warning Sign with Supp. Plate (Encapsulated Lens)	2.000	EA
Loose Riprap, 300 Lb.	110.000	TON
Geotextile under Riprap (Type V, Non-woven)(AOS <0.43)	100.000	SY

EROSION CONTROL ITEMS:

	QUANTITY	UNIT
Agricultural Limestone	0.890	TON
Commercial Fertilizer (13-13-13)	0.450	TON
Ammonium Nitrate	0.230	TON
Seeding	0.940	AC
Vegetative Materials for Mulch	2.670	TON
Solid Sodding	195.000	SY
Portland Cement Concrete Paved Ditch	19.000	CY
Temporary Silt Fence (Type I or II)(AOS 0.15-0.84)	860.000	LF

Wattles, 20"	220.000	LF
Loose Riprap, 200 Lb.	40.000	TON
Geotextile under Riprap (Type V, Non-Woven)(AOS <0.43)	40.000	SY