



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS**

County	Wayne
Project No.	SABP-77(01)
Road Name.	Chicora-Greene County Line Road

BIDS RECEIVED: TUESDAY, OCTOBER 14, 2025 AT 10:00 AM IN THE BOARDROOM AT WAYNESBORO, MS

Project Description: 0.166 miles of BOX BRIDGE and APPROACHES

ROADWAY ITEMS:

MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF OBSTRUCTIONS	1.000	LS
REMOVAL OF BRIDGE @ STA. 205+52	1.000	UN
UNCLASSIFIED EXCAVATION (FM)	1,521.000	CY
MUCK EXCAVATION (FM)	253.000	CY
BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 9-6)	3,391.000	CY
CHANNEL EXCAVATION (FM)	223.000	CY
TEMPORARY STREAM DIVERSION	1.000	EA
CRUSHED STONE (SIZE 825)	899.000	TON
HOT MIX ASPHALT, ST, 9.5 MM	176.000	TON
HOT MIX ASPHALT, ST, 19 MM	537.000	TON
FILTER MATERIAL FOR FILTER BEDS, TYPE "A"	455.000	TON
ROADWAY CONSTRUCTION SURVEYING	1.000	LS
RIGHT-OF-WAY MARKERS (TYPE II)	14.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
4" WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE) (60 MILS)	0.331	MI
4" WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW) (90 MILS)	1,750.000	LF
TWO-WAY YELLOW REFLECTIVE HIGH PERFORMANCE RAISED MARKERS	23.000	EA
REFLECTORIZED TRAFFIC WARNING SIGN (ENCAPSULATED LENS)	2.000	EA
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	4.000	EA

EROSION CONTROL ITEMS:

AGRICULTURAL LIMESTONE	3.300	TON
COMMERCIAL FERTILIZER (13:13:13)	1.650	TON
SEEDING	1.650	AC
VEGETATIVE MATERIALS FOR MULCH	3.300	TON
TEMPORARY GRASSING	1.650	AC
SOLID SODDING	100.000	SY
TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84)	1,900.000	LF
WATTLES, 12"	200.000	LF
LOOSE RIPRAP, (200 LB.)	295.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, AOS <0.43 (NON-WOVEN)	455.000	SY

BOX BRIDGE ITEMS:

BOX BRIDGE CONCRETE, CLASS "BB"
REINFORCEMENT

275.230	CY
54,566.060	LB