



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS**

County	Bolivar
Project No.	SAP-06(2)M
Road Name.	Shelby-Deeson Road & Parchman Road

BIDS RECEIVED: Friday, October 31, 2025 at 10:00 am in the Bolivar Co. Annex Bldg at Cleveland, MS

Project Description: 13.205 miles of MAINTENANCE (OTHER THAN BRIDGE)

ROADWAY ITEMS:

MOBILIZATION	1.000	LS
UNCLASSIFIED EXCAVATION (F.M.)	623.000	CY
GRANULAR MATERIAL (LVM) (CLASS 4, GROUP B)	5,810.000	CY
CRUSHED STONE #610	1,009.000	TON
ASPHALT, ST 19mm (BASE REPAIR)	247.000	TON
ASPHALT, ST 19mm (EDGE REPAIR)	52.000	TON
COLD MILLING OF BITUMINOUS PAVEMENT, ALL DEPTHS	165.000	SY
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
4" WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE) (60 MIL)	26.191	MI
4" WIDE THERMOPLASTIC TRAFFIC STRIPE (SKIP YELLOW) (90 MIL)	10.708	MI
4" WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW) (90 MIL)	49,764.000	LF
THERMOPLASTIC LEGEND (WHITE) (120 MIL)	1,080.000	LF
TWO-WAY YELLOW REFLECTIVE HIGH PERFORMANCE RAISED MARKERS	1,129.000	EA
REFLECTORIZED TRAFFIC WARNING SIGN (ENCAPSULATED LENS)	18.000	EA
REFLECTORIZED TRAFFIC REGULATORY SIGN (ENCAPSULATED LENS)	18.000	EA
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	4.000	EA