



OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)

AND

COUNTY BOARD OF SUPERVISORS

County Bolivar

Project No. SAP-06(51)

Road Name. Bunge Road

Bolivar

BIDS RECEIVED: Monday, May 6, 9:30 am @ Courthouse Annex Building in Cleveland, MS

Project Description: 0.047 miles of BOX BRIDGE & APPROACHES

Roadway Items:

MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF PRECAST BRIDGE @ 20+15.00	1.000	UN
UNCLASSIFIED EXCAVATION (FM)	127.000	CY
BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 9)	1,077.000	CY
TEMPORARY STREAM DIVERSION	1.000	EA
CRUSHED STONE	323.000	TON
HOT MIX ASPHALT, ST 9.5mm	45.000	TON
HOT MIX ASPHALT, ST 19mm	63.000	TON
18" REINFORCED CONCRETE PIPE, CLASS III	32.000	LF
48" REINFORCED CONCRETE PIPE, CLASS III	32.000	LF
18" REINFORCED CONCRETE PIPE, END SECTION	1.000	EA
48" REINFORCED CONCRETE PIPE, END SECTION	1.000	EA
18" BRANCH CONNECTION (R.C.P. TO WINGWALL OF BOX)	1.000	EA
48" BRANCH CONNECTION (R.C.P. TO WINGWALL OF BOX)	1.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
4" WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE) (60 MILS)	0.093	MI
4" WIDE THERMOPLASTIC TRAFFIC STRIPE (SKIP YELLOW) (90 MILS)	0.047	MI
TWO-WAY YELLOW REFLECTIVE HIGH PERFORMANCE RAISED MARKERS	3.000	EA

EROSION CONTROL ITEMS:

COMMERCIAL FERTILIZER (13:13:13)	0.190	TON
SEEDING	0.500	AC
VEGETATIVE MATERIALS FOR MULCH	1.000	TON
TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84)	764.000	LF
WATTLES, 20"	120.000	LF
LOOSE RIPRAP, 300 LB.	305.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, AOS 0.21-0.43	484.000	SY

BRIDGE ITEMS:

BOX BRIDGE CONCRETE, CLASS "BB"	316.780	CY
REINFORCEMENT	68,061.360	LB