



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS**

County Bolivar

Project No. SAP-06(9)S

Road Name. Site "A" Litton Road & Site "B" Shaw-Skene Road

BIDS RECEIVED: THURSDAY, AUGUST 21, 2025 AT 10:00 AM IN THE BOLIVAR CO. ANNEX BLDG. AT CLEVELAND, MS

Project Description: 15.513 miles of BASE and SURFACING

ROADWAY ITEMS:

Mobilization	1.000	LS
Unclassified Excavation (F.M.)	780.000	CY
Granular Material (LVM), (Class 4, Group B)	6,826.000	CY
Crushed Stone, Size 610	1,018.000	TON
Asphalt, Type ST, Mixture 9.5 mm (Base Repair)	515.000	TON
Asphalt, Type ST, Mixture 9.5 mm (Leveling)	2,333.000	TON
Emulsified Asphalt for Micro-Surfacing	68,261.000	GAL
Aggregate for Micro-Surfacing (Type III)	2,295.000	TON
Maintenance of Traffic	1.000	LS
Additional Construction Signs	0.000	SF
4"-Wide Thermoplastic Edge Stripe (Continuous White) (60 MILS)	31.049	MI
4"-Wide Thermoplastic Traffic Stripe (Skip Yellow) (90 MILS)	15.446	MI
4"-Wide Thermoplastic Traffic Stripe (Continuous Yellow) (90 MILS)	7,890.000	LF
Thermoplastic Legend (White) (120 MILS)	660.000	LF
Two-Way Yellow Reflective High Performance Raised Markers	1,032.000	EA
Reflectorized Traffic Warning Sign (Encapsulated Lens)	11.000	EA
Reflectorized Traffic Regulatory Sign (Encapsulated Lens)	2.000	EA
Reflectorized Traffic Object Marker (Encapsulated Lens) (Type 3)	8.000	EA