



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS**

County	Carroll
Project No.	SAP-08(9)M
Road Name.	ROADS "A"-"G"

BIDS RECEIVED: FRIDAY, OCTOBER 3, 2025 AT 10:00 AM IN THE COURTHOUSE AT CARROLLTON, MS

Project Description: 11.597 miles of MAINTENANCE (OTHER THAN BRIDGE)

ROADWAY ITEMS:

Mobilization	1.000	LS
Clearing and Grubbing	1.000	LS
Removal of Pipe (All Sizes)	40.000	LF
Unclassified Excavation (FM)	289.000	CY
Borrow Excavation (Contractor-Furnished FME, Class 9)	450.000	CY
Granular Material (Class 4, Group B)	622.000	TON
Crushed Stone, Size 610	110.000	TON
Asphalt, ST, 12.5 mm	4,314.000	TON
Asphalt, ST, 12.5 mm (Base Repair)	324.000	TON
Asphalt, ST, 12.5 mm (Leveling)	2,072.000	TON
Cold Milling of Bituminous Pavement, All Depths	931.000	SY
Class "B" Structural Concrete, Minor Structures	4.000	CY
24" Reinforced Concrete Pipe, Class III	48.000	LF
72" Reinforced Concrete Pipe, Class III	16.000	LF
24" Reinforced Concrete Pipe, End Section	2.000	EA
72" Reinforced Concrete Pipe, End Section	1.000	EA
Maintenance of Traffic	1.000	LS
Additional Construction Signs	0.000	SF
4" Wide Thermoplastic Edge Stripe (Continuous White) (90 MILS)	23.055	MI
4"-Wide Thermoplastic Traffic Stripe (Skip Yellow) (120 MILS)	2.739	MI
4"-Wide Thermoplastic Traffic Stripe (Continuous Yellow) (120 MILS)	104,240.000	LF
Thermoplastic Legend (White) (120 MILS)	736.000	LF
Two-Way Yellow Reflective High-Performance Raised Markers	1,050.000	EA
Reflectorized Traffic Warning Sign (Encapsulated Lens)	59.000	EA
Reflectorized Traffic Regulatory Sign (Encapsulated Lens)	12.000	EA
Reflectorized Traffic Object Marker (Encapsulated Lens) (Type 3)	20.000	EA
Reflectorized Traffic Warning Sign with Supp. Plate (Encapsulated Lens)	12.000	EA
Flowable Fill, Non-Excavatable	10.000	CY

EROSION CONTROL ITEMS:

Agricultural Limestone	1.000	TON
Commercial Fertilizer (13:13:13)	0.500	TON
Ammonium Nitrate	0.050	TON
Seeding	0.500	AC

Vegetative Materials for Mulch	1.000	TON
Excelsior Blanket	200.000	SY
Temporary Silt Fence (Type II) (AOS 0.15-0.84)	500.000	LF
Wattles, 12"	200.000	LF
Loose Riprap, 300 LB	320.000	TON
Geotextile under RipRap, Type V, Non-Woven, AOS <0.43	345.000	SY