



OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)

AND

COUNTY BOARD OF SUPERVISORS

County Chickasaw
Project No. SAP-09(21)S
Road Name. Road A - Road F

BIDS RECEIVED: MONDAY, MAY 4, 2026 AT 10:00 AM IN THE BOARDROOM AT HOUSTON, MS

Project Description: 9.43 miles of MAINTENANCE (OTHER THAN BRIDGE) Base Repair & Reseal

Roadway Items:

MOBILIZATION	1.000	LS
UNCLASSIFIED EXCAVATION (FM)	2,638.000	CY
GEOTEXTILE FABRIC STABILIZATION (TYPE V) (AOS <0.43) (NON-WOVEN)	2,420.000	SY
GRANULAR MATERIAL (FM) (CLASS 5, GROUP "C")	626.000	CY
CRUSHED STONE 3/4" & DOWN (FM)	1,682.000	CY
ASPHALT, ST, 19 MM BASE REPAIR	1,866.000	TON
ASPHALT, ST, 9.5MM, EDGE REPAIR	48.000	TON
ASPHALT, ST, 9.5MM, LEVELING	500.000	TON
POLYMERIZED EMULSIFIED ASPHALT, GRADE CRS-2P	34,471.000	GAL
SEAL AGGREGATE COVER MATERIAL, SIZE 7, CRUSHED STONE	795.000	CY
BLOTTER MATERIAL	114.000	CY
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
4 " - WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE) (60 MILS)	18.976	MI
4 " - WIDE THERMOPLASTIC TRAFFIC STRIPE (SKIP YELLOW) (90 MILS)	4.098	MI
4 " - WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW) (90 MILS)	69,289.000	LF
THERMOPLASTIC LEGEND (WHITE) (120 MILS)	450.000	LF
TWO-WAY YELLOW REFLECTIVE HIGH PERFORMANCE RAISED MARKERS	115.000	EA
REFLECTORIZED TRAFFIC WARNING SIGN (ENCAPSULATED LENS)	31.000	EA
REFLECTORIZED TRAFFIC REGULATORY SIGN (ENCAPSULATED LENS)	19.000	EA
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	84.000	EA
REFLECTORIZED TRAFFIC WARNING SIGN WITH SUPP. PLATE (ENCAPSULATED LENS)	1.000	EA