



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)  
AND  
COUNTY BOARD OF SUPERVISORS**

**County** Coahoma  
**Project No.** SAP-14(21)M  
**Road Name.** Stovall Road and Friars Point Road

**BIDS RECEIVED:** WEDNESDAY, JUNE 24, 2026 AT 10:00 AM IN THE COAHOMA COUNTY COURTHOUSE AT CLARKSDALE, MS

**Project Description:** 8.093 miles of MAINTENANCE (OTHER THAN BRIDGE)

<b>ROADWAY ITEMS:</b>	<b>QUANTITY</b>	<b>UNIT</b>
Mobilization	1.000	LS
Clearing and Grubbing	1.000	LS
Removal of Curb and Gutter	954.000	LF
Unclassified Excavation (FM)	1,294.000	CY
Borrow Excavation (Contractor-Furnished FME, Class 9)	10.000	CY
Light Linear Grading	401.000	STA
Crushed Stone No. 610	5,987.000	TON
Asphalt, Type ST, Mixture 12.5 mm (Edge Repair)	50.000	TON
Asphalt, Type ST, Mixture 12.5 mm (Surface)	4,934.000	TON
Asphalt, Type ST, Mixture 19 mm (Base Repair)	1,228.000	TON
Cold Milling of Bituminous Pavement, All Depths	10,320.000	SY
Castings	346.000	LB
Gratings	385.000	LB
Combination Concrete Curb and Gutter (Type 3B)	954.000	LF
Maintenance of Traffic	1.000	LS
Additional Construction Signs	0.000	SF
4"-Wide Thermoplastic Edge Stripe (Continuous White) (60 mil)	5.630	MI
4"-Wide Thermoplastic Traffic Stripe (Skip Yellow) (60 mil)	1.827	MI
4"-Wide Thermoplastic Traffic Stripe (Continuous Yellow) (90 mil)	14,604.000	LF
Thermoplastic Legend (White) (120 mil)	99.000	LF
Two-Way Yellow Reflective High-Performance Raised Markers	382.000	EA
Reflectorized Traffic Warning Sign (Encapsulated Lens)	11.000	EA
Reflectorized Traffic Regulatory Sign (Encapsulated Lens)	9.000	EA
Loose Riprap, 300 lb	120.000	TON
Geotextile under Riprap, Type V, Non-Woven, AOS<0.43	202.000	SY