



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS**

County	Covington
Project No.	SAP-16(15)M
Road Name.	Williamsburg-Bassfield
BIDS RECEIVED:	Monday, December 1st at 10:00 AM in the Boardroom at Collins Ms
Project Description:	0.308 miles of OVERLAY

ROADWAY ITEMS:

MOBILIZATION	1.000	LS
UNCLASSIFIED EXCAVATION (FM)	28.000	CY
GRANULAR MATERIAL (LVM) (CL. 5, GP. C)	34.000	CY
HOT MIX ASPHALT, ST, 12.5 MM (EDGE REPAIR)	3.000	TON
HOT MIX ASPHALT, ST, 19 MM (BASE REPAIR)	55.000	TON
HOT MIX ASPHALT, ST, 9.5 MM, OVERLAY	438.000	TON
HOT MIX ASPHALT, ST, 9.5 MM, LEVELING	74.000	TON
EMULSIFIED ASPHALT, GRADE CRS-2P	1,990.000	GAL
COARSE AGGREGATE COVER MATERIAL, SIZE 56, TYPE CRUSHED STONE	83.000	CY
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
4" WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE) (60 MIL)	0.617	MI
4" WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW) (90 MIL)	3,256.000	LF
TWO-WAY YELLOW REFLECTIVE HIGH PERFORMANCE RAISED MARKERS	40.000	EA
REFLECTORIZED TRAFFIC WARNING SIGN (ENCAPSULATED LENS)	1.000	EA
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	2.000	EA