



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)  
AND  
COUNTY BOARD OF SUPERVISORS**

<b>County</b>	Covington
<b>Project No.</b>	SAP-16(25)S
<b>Road Name.</b>	Old Hwy 84 - Leaf River Church

<b>BIDS RECEIVED:</b>	Monday, March 2, 2026 in the Board Room at Collins, Ms
<b>Project Description:</b>	1.761 miles of RESEAL

**ROADWAY ITEMS:**

MOBILIZATION	1.000	LS
UNCLASSIFIED EXCAVATION (FM)	46.000	CY
HOT MIX ASPHALT, (ST) (12.5mm)(EDGE REPAIR)	18.000	TON
HOT MIX ASPHALT, (ST) (19 mm) (BASE REPAIR)	92.000	TON
HOT MIX ASPHALT, (ST) (9.5 mm), LEVELING	258.000	TON
EMULSIFIED ASPHALT, GRADE CRS-2P	10,293.000	GAL
SEAL AGGREGATE COVER MATERIAL, SIZE 7, CRUSHED STONE	254.000	CY
BLOTTER MATERIAL	36.000	CY
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
4 " WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE) ( 60 mil )	3.477	MI
4 " WIDE THERMOPLASTIC TRAFFIC STRIPE (SKIP YELLOW) (90 mil)	0.454	MI
4 " WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW) (90 mil )	15,600.000	LF
THERMOPLASTIC LEGEND (WHITE) (120 mil)	600.000	LF
TWO-WAY YELLOW REFLECTIVE HIGH PERFORMANCE RAISED MARKERS	116.000	EA
REFLECTORIZED TRAFFIC WARNING SIGN (ENCAPSULATED LENS)	13.000	EA
REFLECTORIZED TRAFFIC REGULATORY SIGN (ENCAPSULATED LENS)	4.000	EA