



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS**

County	Covington
Project No.	SAP-16(69)
Road Name.	Ora Swamp

BIDS RECEIVED: TUESDAY, SEPTEMBER 15, 2026 AT 10:00 AM IN THE BOARDROOM AT COLLINS, MS

Project Description: 0.151 miles of GRADE DRAIN BASE and SURFACING

ROADWAY ITEMS:

	QUANTITY	UNIT
MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 9)	5,200.000	CY
GRANULAR MATERIAL (L.V.M.), (CL. 5, GP. "C")	1,202.000	CY
HOT MIX ASPHALT, ST. 9.5 mm	202.000	TON
HOT MIX ASPHALT, ST. 19 mm	414.000	TON
RIGHT-OF-WAY MARKERS (TYPE I)	4.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
4" WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE) (60 MILS)	0.303	MI
4" WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW) (90 MILS)	1,600.000	LF
THERMOPLASTIC LEGEND (WHITE) (120 MILS)	150.000	LF
THERMOPLASTIC LEGEND (WHITE) (120 MILS)	63.000	SF
TWO-WAY YELLOW REFLECTIVE HIGH PERFORMANCE RAISED MARKERS	12.000	EA
REFLECTORIZED RAILROAD CROSSING (CROSS BUCK) SIGN (ENCAPSULATED LENS)	1.000	EA

EROSION CONTROL ITEMS:

	QUANTITY	UNIT
AGRICULTURAL LIMESTONE	2.800	TON
COMMERCIAL FERTILIZER (13-13-13)	1.400	TON
AMMONIUM NITRATE	0.280	TON
SEEDING	1.400	AC
VEGETATIVE MATERIALS FOR MULCH	1.400	TON
SOLID SODDING	200.000	SY
TEMPORARY SILT FENCE (TYPE II) (AOS 0.15 - 0.84)	1,800.000	LF
WATTLES, 20"	200.000	L.F.
LOOSE RIPRAP, 200 LB.	100.000	TON
GEOTEXTILE UNDER RIPRAP (TYPE V) (AOS < 0.43) (NON-WOVEN)	186.000	SY