



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS**

County Franklin
Project No. SAP-19(15)S
Road Name. "A" - "H"

BIDS RECEIVED: MONDAY, JUNE 8, 2026 AT 10:00 AM IN THE BOARDROOM AT MEADVILLE, MS

Project Description: 26.652 miles of RESEAL Edge Repair, Base Repair, Leveling, Reseal, Sign & Stripe

ROADWAY ITEMS:

	QUANTITY	UNIT
MOBILIZATION	1.000	LS
UNCLASSIFIED EXCAVATION (FM)	569.000	CY
LIGHT LINEAR GRADING	10.000	STA
GRANULAR MATERIAL (LVM) (CLASS 5, GROUP C)	100.000	CY
ASPHALT, ST, 19 MM, BASE REPAIR	899.000	TON
ASPHALT, ST, 19 MM, EDGE REPAIR	262.000	TON
ASPHALT, ST, 9.5 MM, LEVELING	460.000	TON
EMULSIFIED ASPHALT, GRADE CRS-2P	102,186.000	GAL
SEAL AGGREGATE COVER MATERIAL, SIZE 89, TYPE CRUSHED STONE	2,703.000	CY
BLOTTER MATERIAL	485.000	CY
SCRUB SEAL	82,122.000	SY
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
4" WIDE COLD PLASTIC EDGE STRIPE (CONTINUOUS WHITE)	0.584	MI
4" WIDE COLD PLASTIC TRAFFIC STRIPE (SKIP YELLOW)	0.275	MI
4" WIDE COLD PLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW)	1,654.000	LF
4" WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE) (60 MIL)	53.036	MI
4" WIDE THERMOPLASTIC TRAFFIC STRIPE (SKIP YELLOW) (90 MIL)	13.169	MI
4" WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW) (90 MIL)	200,964.000	LF
THERMOPLASTIC LEGEND (WHITE) (120 MIL)	3,993.000	LF
TWO-WAY CLEAR REFLECTIVE HIGH PERFORMANCE RAISED MARKERS	450.000	EA
TWO-WAY YELLOW REFLECTIVE HIGH PERFORMANCE RAISED MARKERS	1,812.000	EA
REFLECTORIZED TRAFFIC WARNING SIGN (ENCAPSULATED LENS)	55.000	EA
REFLECTORIZED TRAFFIC REGULATORY SIGN (ENCAPSULATED LENS)	6.000	EA
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	40.000	EA