



OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)

AND

COUNTY BOARD OF SUPERVISORS

County Franklin
Project No. SAP-19(75)
Road Name. Berrytown Road

BIDS RECEIVED: TUESDAY, MAY 12, 2026 AT 10:00 AM IN THE BOARDROOM AT MEADVILLE, MS

Project Description: 0.17 miles of GRADE DRAIN BASE & SURFACING

Roadway Items:

MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF ASPHALT PAVEMENT (ALL DEPTHS)	600.000	SY
UNCLASSIFIED EXCAVATION (FM)	1,200.000	CY
BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 9-10)	2,551.000	CY
GRANULAR MATERIAL (LVM), (CLASS 4, GROUP B)	300.000	CY
CRUSHED STONE SIZE 610, LVM	600.000	CY
HOT MIX ASPHALT, ST, 9.5MM	125.000	TON
HOT MIX ASPHALT, ST,19MM	165.000	TON
6" PERFORATED SEWER PIPE FOR UNDERDRAINS (SDR 23.5)	300.000	LF
6" NON-PERFORATED SEWER PIPE FOR UNDERDRAINS (SDR 23.5)	50.000	LF
FILTER MATERIAL FOR COMBINATION STORM DRAIN AND/OR UNDERDRAINS, TYPE A, LVM	45.000	CY
FILTER MATERIAL FOR COMBINATION STORM DRAIN AND/OR UNDERDRAINS, TYPE B, LVM	675.000	CY
UNDERDRAIN APPURTENANCES (CONCRETE APRON, PRECAST OR CAST IN PLACE)	1.000	EA
GEOTEXTILE FOR SUBSURFACE DRAINAGE, TYPE III, AOS 0.15-0.43	230.000	SY
RIGHT-OF-WAY MARKERS (TYPE I)	4.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
4 " WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE) (60 MILS)	0.210	MI
4 " WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW) (90 MILS)	1,100.000	LF
TWO-WAY YELLOW REFLECTIVE HIGH PERFORMANCE RAISED MARKERS	28.000	EA

EROSION CONTROL ITEMS:

AGRICULTURAL LIMESTONE	2.600	TON
COMMERCIAL FERTILIZER (13-13-13)	1.300	TON
AMMONIUM NITRATE	0.650	TON
SEEDING	1.300	AC
VEGETATIVE MATERIALS FOR MULCH	2.600	TON
TEMPORARY GRASSING	1.300	AC
EXCELSIOR BLANKET	3,000.000	SY
TEMPORARY SILT FENCE, (TYPE II) (AOS 0.15-0.84)	750.000	LF
WATTLES, 12"	1,000.000	LF
WATTLES, 20"	1,000.000	LF
LOOSE RIPRAP, 200 LB.	70.000	TON
GEOTEXTILE UNDER RIPRAP, (TYPE V)(NON-WOVEN) (AOS 0.21-0.43)	105.000	SY